······www.cmit.csiro.au

FSP 1144

FIRE-RESISTANCE TEST ON A FIRE COLLAR CAST INTO A REINFORCED CONCRETE SLAB

In confidence to TRUSS HOLDINGS PTY LTD

15 AUGUST 2005



FSP 1144

FIRE-RESISTANCE TEST ON A FIRE COLLAR CAST INTO A REINFORCED CONCRETE SLAB

In confidence to TRUSS HOLDINGS PTY LTD

15 AUGUST 2005



"Copyright CSIRO 2005 ©"
Copying or alteration of this report without written authorisation from CSIRO is forbidden.

CSIRO – Manufacturing and Infrastructure Technology 14 Julius Avenue, Riverside Corporate Park, North Ryde NSW 2113 Ph: 02 9490 5444 Fax: 02 9490 5528 This Report is subject to binding obligations under which it was prepared. In particular, the Report must not be used:

- as a means of endorsement; or
- in a company prospectus or notification to a Stock Exchange document for capital raising, without the prior written consent of CSIRO.

The Report may be published verbatim and in full, provided that a statement is included on the publication that it is a copy of the Report issued by CSIRO.

Excerpts of the report may not be published.







FIRE-RESISTANCE TEST ON A FIRE COLLAR CAST INTO A REINFORCED CONCRETE SLAB

SPONSORED INVESTIGATION No. FSP 1144

IDENTIFICATION

OF SPECIMEN:

The sponsor identified the specimen as a FireShield Series 3 collar cast into a

reinforced concrete slab, protecting a pipe penetration.

SPONSOR:

Truss Holdings Pty Ltd 161 Railway Parade THORNSIDE QLD

MANUFACTURER:

Fire Protection Solutions Pty Ltd

161 Railway Parade THORNSIDE QLD

TEST STANDARDS: Australian Standard 1530, Methods for fire tests on building materials,

components and structures,

Part 4: Fire-resistance tests of elements of building construction -1997;

Australian Standard 4072, Components for the protection of openings in fire-

resistant separating elements,

Part 1: Service penetrations and control joints -1992.

TEST NUMBER:

FS 3738/2784

TESTED:

The fire-resistance test was conducted on 23 March 2005.

DESCRIPTION OF SPECIMEN:

GENERAL

The specimen comprised a 1150-mm x 1150-mm x 150-mm thick reinforced concrete slab penetrated by one large diameter uPVC pipe, protected by a cast-in Fireshield collar. The cast-in collar was cast into the existing reinforced concrete slab using a fast curing cement that was backfilled into a pre-cored

hole.



MANUFACTURING & INFRASTRUCTURE TECHNOLOGY



315-mm Series 3 Cast-in FireShield Collar Penetration -FS3S - 315A1 (315-mm uPVC pipe)

The Series 3 Cast-in FireShield Collar consisted of a 1.2-mm thick steel case, 355-mm in diameter and 190-mm in height.

The collar incorporated 6 springs, these were pivoted at the top of the spring cavity and restrained by a nylon fusible link with a melting temperature of 75 degrees Celsius.

A soft intumescent wrap lined the internal circumference of the collar. The wrap was 10-mm thick x 180-mm wide, and weighed approximately 2860 grams. The wrap was covered on the outside with a stainless steel mesh 0.35-mm thick and 180-mm wide, and on the inside with a 0.35-mm thick x 57-mm wide Colan Type E fibreglass sleeve, extending down from the top of the collar 150-mm.

A nominal 315-mm OD uPVC Vinidex stormwater pipe was fitted through the collar's sleeve. The pipe projected vertically 2000-mm above the slab and approximately 150-mm into the furnace chamber. The pipe above the slab was supported at 1000-mm intervals. The pipe was open at the top and capped at the exposed end.

A concrete hob, approximately 100-mm high, was cast around the portion of the collar projecting above the slab, in order to maintain a minimum 50-mm concrete cover around all of the projecting steel case of the collar.

DIMENSIONS

The specimen's overall dimension was 1150-mm x 1150-mm to suit the opening in the specimen frame.

ORIENTATION

The reinforced concrete slab was placed horizontally on top of the furnace chamber.

DOCUMENTATION: The following documents were supplied by the sponsor as a complete description of the specimen and should be read in conjunction with this report:

Specification, dated 31 May 2005, by Fireball International Pty Ltd

Drawings file Nos. FSTD73 and FSTD73A, both undated by Fireball Collars Pty Ltd.

Confidential information about the test specimen has been submitted and is retained at the Division of Manufacturing and Infrastructure Technology.

EQUIPMENT:

FURNACE

The furnace had a nominal opening of 1000-mm x 1000-mm for attachment of vertical or horizontal specimens.

The furnace was lined with refractory bricks and materials with the thermal properties as specified in AS 1530.4-1997 and was heated by combustion of a mixture of natural gas and air.



MANUFACTURING & INFRASTRUCTURE TECHNOLOGY



TEMPERATURE

The temperature in the furnace chamber was measured by four type K, 3-mm diameter, 310 stainless steel Mineral Insulated Metal Sheathed (MIMS) thermocouples. Each thermocouple was housed in high-nickel steel tubes opened at the exposed end.

The temperature in the furnace chamber was also measured by two plate thermometer assemblies as specified in ISO 834.1 – 1999.

The temperatures of the specimen were measured by glass-fibre insulated and sheathed K-type thermocouples with a wire diameter of 0.5-mm.

MEASUREMENT SYSTEM

The primary measurement system comprised a multiple-channel datalogger scanning at one-minute intervals during the test.

AMBIENT TEMPERATURE:

The temperature of the furnace chamber was 22°C at the commencement of the test.

DEPARTURE FROM

TEST STANDARDS: There were no departures from the requirements of AS 1530.4-1997 and AS 4072.1-1992.

TERMINATION OF TEST:

The test was terminated at 185 minutes by agreement with the sponsor.

TEST RESULTS:

CRITICAL OBSERVATIONS

The following observations were made during the fire-resistance test:

- 1 minute Smoke is fluing from the top of the pipe.
- 2 minutes Smoke has ceased fluing from the pipe.
- 3 minutes Smoke has started to flue from the pipe again.
- 6 minutes Smoke quantity fluing from the pipe has decreased.
- 11 minutes Smoke has ceased fluing from the pipe.
- 25 minutes Small amount of smoke has started to flue from the pipe.
- 60 minutes No apparent change to the specimen.
- 120 minutes No apparent change to the specimen.
- 174 minutes Smoke quantity fluing from the pipe has increased.
- 181 minutes Test terminated.



MANUFACTURING & INFRASTRUCTURE TECHNOLOGY



FURNACE TEMPERATURE

Figure 1 shows the standard curves of temperature versus time for heating the furnace chamber and the actual curves of average and maximum temperature versus time recorded during the heating period.

SPECIMEN TEMPERATURE

Figure 2 shows the curve of maximum temperature versus time associated with the penetration.

PERFORMANCE

Performance observed in respect of the following heating conditions and general AS 1530.4-1997 criteria:

Penetration A – 315-mm Series 3 Cast-in FireShield Collar FS3S - 315A1 (315-mm uPVC pipe)

Structural adequacy

not applicable

Integrity

no failure at 185 minutes

Insulation

no failure at 185 minutes

For the purposes of AS 1530.4 –1997, the results only relate to the behaviour of the element of construction under the particular conditions of test; they are not intended to be the sole criteria for assessing the potential fire performance of the element in use, nor do they reflect the actual behaviour in fires.

FIRE-RESISTANCE LEVEL:

For the purpose of building regulations in Australia, the fire-resistance levels (FRL) of the test specimen is -/180/180.

The fire-resistance level is applicable for exposure to fire from the same side as tested.

APPENDICES:

APPENDIX 1

Photograph 1 – Specimen (exposed side) prior to testing	Page	7
Photograph 2 – Specimen (unexposed side) prior to testing	Page	7
Photograph 3 – Specimen at 61 minutes into the test	Page	8
Photograph 4 – Specimen at 121 minutes into the test	Page	8
Photograph 5 – Specimen at 181 minutes into the test	Page	9
Photograph 6 – Specimen (exposed side) after the completion of testing.	Page	9



MANUFACTURING & INFRASTRUCTURE TECHNOLOGY



APPENDIX 2	
Figure 1 FURNACE TEMPERATURE	Page 10
Figure 2 SPECIMEN TEMPERATURE- Maximum temperature associated with the penetration	Page 11
APPENDIX 3	
Drawing file No. FSTD73, undated, by Fireball Collars Pty Ltd	Page 12
Drawing file No. FSTD73A, undated, by Fireball Collars Pty Ltd	Page 13
APPENDIX 4	
A copy of Certificate of Test No. 1923	Page 14

TESTED BY:


Chris Wojcik Testing Officer Garry Collins Manager, Fire Testing and Assessment

15 AUGUST 2005











Photograph 1 - Specimen (exposed side) prior to testing.




Photograph 2 - Specimen (unexposed side) prior to testing.







Photograph 3 - Specimen at 61 minutes into the test.




Photograph 4 - Specimen at 121 minutes into the test.











Photograph 5 - Specimen at 181 minutes into the test.



Photograph 6 - Specimen (exposed side) after the completion of testing.








































Certificate of Test

No. 1923

"Copyright CSIRO 2005 ©"
Copyring or alteration of this report without written authorisation from CSIRO is forbidden.

This is to certify that the element of construction described below was tested by the CSIRO Division of Manufacturing and Infrastructure Technology in accordance with Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4-1997 and Australian Standard 4072, Components for the protection of openings in fire-resistant separating elements, Part 1: Service penetrations and control joints -1992, on behalf of

Truss Holdings Pty Ltd 161 Railway Parade THORNSIDE QLD

A full description of the test specimen and the complete test results are detailed in the Division's sponsored investigation report numbered FSP 1144.

Product Name: Penetration -

315-mm Series 3 Cast-in FireShield Collar

FS3S - 315A1 (315-mm uPVC pipe)

Description:

The Series 3 Cast-in FireShield Collar consisted of a 1.2-mm thick steel case, 355-mm in diameter

and 190-mm in height.

The collar incorporated 6 springs, these were pivoted at the top of the spring cavity and restrained

by a nylon fusible link with a melting temperature of 75 degrees Celsius.

A soft intumescent wrap lined the internal circumference of the collar. The wrap was 10-mm thick x 180-mm wide, and weighed approximately 2860 grams. The wrap was covered on the outside with a stainless steel mesh 0.35-mm thick and 180-mm wide, and on the inside with a 0.35-mm thick x 57-mm wide Colan Type E fibreglass sleeve, extending down from the top of the collar 150-mm. A nominal 315-mm OD uPVC Vinidex stormwater pipe was fitted through the collar's sleeve. The pipe projected vertically 2000-mm above the slab and approximately 150-mm into the furnace chamber. The pipe above the slab was supported at 1000-mm intervals. The pipe was open at the top and capped at the exposed end.

A concrete hob, approximately 100-mm high, was cast around the portion of the collar projecting above the slab, in order to maintain a minimum 50-mm concrete cover around all of the projecting

steel case of the collar.

Construction is detailed in drawing file No. FSTD73A, undated, by Fireball Collars Pty Ltd.

The element of construction described above satisfied the following criteria for fire-resistance for the period stated.

Structural Adequacy

not applicable

Integrity

no failure at 185 minutes

Insulation

no failure at 185 minutes

and therefore for the purpose of Building Regulations in Australia, achieved a fire-resistance level (FRL) of -/180/180. The FRL is applicable for exposure to fire from the same side as tested.

Testing Officer:

Chris Wojcik

Date of Test: 23 March 2005

Issued on the 15th day of August 2005 without alterations or additions.

Garry E Collins

Manager, Fire Testing and Assessments



This laboratory is accredited (Accreditation No. 3632) by the National Association of Testing Authorities, Australia. The tests reported herein have been performed in accordance with its terms of accreditation.



CSIRO Manufacturing & Infrastructure Technology

14 Julius Avenue, Riverside Corporate Park, North Ryde NSW 2113 AUSTRALIA Telephone: 61 2 9490 5444 Facsimile: 61 2 9490 5555



MANUFACTURING & INFRASTRUCTURE TECHNOLOGY



Certificate of Test

No. 1923

"Copyright CSIRO 2005 ©"
Copying or alteration of this report without written authorisation from CSIRO is forbidden.

This is to certify that the element of construction described below was tested by the CSIRO Division of Manufacturing and Infrastructure Technology in accordance with Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4-1997 and Australian Standard 4072, Components for the protection of openings in fire-resistant separating elements, Part 1: Service penetrations and control joints -1992, on behalf of

Truss Holdings Pty Ltd 161 Railway Parade THORNSIDE QLD

A full description of the test specimen and the complete test results are detailed in the Division's sponsored investigation report numbered FSP 1144.

Product Name: Penetration - 315-mm Series 3 Cast-in FireShield Collar

FS3S - 315A1 (315-mm uPVC pipe)

Description: The Series

The Series 3 Cast-in FireShield Collar consisted of a 1.2-mm thick steel case, 355-mm in diameter

and 190-mm in height.

The collar incorporated 6 springs, these were pivoted at the top of the spring cavity and restrained

by a nylon fusible link with a melting temperature of 75 degrees Celsius.

A soft intumescent wrap lined the internal circumference of the collar. The wrap was 10-mm thick x 180-mm wide, and weighed approximately 2860 grams. The wrap was covered on the outside with a stainless steel mesh 0.35-mm thick and 180-mm wide, and on the inside with a 0.35-mm thick x 57-mm wide Colan Type E fibreglass sleeve, extending down from the top of the collar 150-mm. A nominal 315-mm OD uPVC Vinidex stormwater pipe was fitted through the collar's sleeve. The pipe projected vertically 2000-mm above the slab and approximately 150-mm into the furnace chamber. The pipe above the slab was supported at 1000-mm intervals. The pipe was open at the top and capped at the exposed end.

A concrete hob, approximately 100-mm high, was cast around the portion of the collar projecting above the slab, in order to maintain a minimum 50-mm concrete cover around all of the projecting

steel case of the collar.

Construction is detailed in drawing file No. FSTD73A, undated, by Fireball Collars Pty Ltd.

The element of construction described above satisfied the following criteria for fire-resistance for the period stated.

Structural Adequacy

not applicable

Integrity

no failure at 185 minutes

Insulation

no failure at 185 minutes

and therefore for the purpose of Building Regulations in Australia, achieved a fire-resistance level (FRL) of -/180/180. The FRL is applicable for exposure to fire from the same side as tested.

Testing Officer:

Chris Wojcik

Date of Test:

23 March 2005

Issued on the 15th day of August 2005 without alterations or additions.

Garry E Collins

Manager, Fire Testing and Assessments



This laboratory is accredited (Accreditation No. 3632) by the National Association of Testing Authorities, Australia. The tests reported herein have been performed in accordance with its terms of accreditation.



CSIRO Manufacturing & Infrastructure Technology

14 Julius Avenue, Riverside Corporate Park, North Ryde NSW 2113 AUSTRALIA Telephone: 61 2 9490 5444 Facsimile: 61 2 9490 5555