

# Fire-resistance test on retrofit fire collars protecting a plasterboard wall penetrated by services

# **Test Report**

Author: Peter Gordon Report number: FSP 2120

**Date:** 7 September 2020

Client: IG6 Pty Ltd as trustee for the IG6 IP Trust

Commercial-in-confidence



# Inquiries should be addressed to:

Fire Testing and Assessments Author The Client

NATA Registered Laboratory Infrastructure Technologies IG6 Pty Ltd as trustee for the IG6 IP Trust
14 Julius Avenue 14 Julius Avenue 3 Skirmish Court

North Ryde, NSW 2113 North Ryde, NSW 2113 Victoria Point QLD 4165
Telephone +61 2 9490 5444 Telephone +61 2 9490 5500 Telephone: +61 7 3390 5420

## Report Status and Revision History:

VERSION	STATUS	DATE	DISTRIBUTION	ISSUE NUMBER
Revision A	Draft for review	27/08/2020	CSIRO / Client	FSP 2120
Revision B	Final for issue	07/09/2020	CSIRO / Client	FSP 2120

### **Report Authorisation:**

AUTHOR	REVIEWED BY	AUTHORISED BY
Peter Gordon	Glenn Williams	Brett Roddy
Pelolonon	J. Williams	B. Rong
7 September 2020	7 September 2020	7 September 2020

#### Use of Reports - Testing

This report is subject to binding obligations under which it was prepared. In particular, the Report must not be used:

- as a means of endorsement; or
- in a company prospectus or notification to a Stock Exchange document for capital raising, without the prior written consent of CSIRO.

The Report may be published verbatim and in full, provided that a statement is included on the publication that it is a copy of the Report issued by CSIRO.

Excerpts of the Report may not be published.

#### Use of Reports – Consultancy

This report is subject to binding obligations under which it was prepared. In particular, the Report may only be used for the following purposes:

- the information in the Report may be used by the party that commissioned the Report for its internal business operations (but not licensing to third parties);
- the report may be copied for distribution within the organisation that commissioned the Report;
- copies of the Report (or extracts of the Report) may be distributed to contractors and agents of the organisation that commissioned the Report who have a need for the Report for its internal business operations. Any extracts of the Report distributed for this purpose must clearly note that the extract is part of a larger Report held by the organisation that commissioned the Report and which has been prepared by CSIRO.

The name, trademark or logo of the CSIRO must not be used without the prior written consent of CSIRO.

The Report must not be used as a means of endorsement without the prior written consent of CSIRO.

### Copyright and disclaimer

© 2020 CSIRO To the extent permitted by law, all rights are reserved, and no part of this publication covered by copyright may be reproduced or copied in any form or by any means except with the written permission of CSIRO.

#### Important disclaimer

CSIRO advises that the information contained in this publication comprises general statements based on scientific research. The reader is advised and needs to be aware that such information may be incomplete or unable to be used in any specific situation. No reliance or actions must therefore be made on that information without seeking prior expert professional, scientific and technical advice. To the extent permitted by law, CSIRO (including its employees and consultants) excludes all liability to any person for any consequences, including but not limited to all losses, damages, costs, expenses and any other compensation, arising directly or indirectly from using this publication (in part or in whole) and any information or material contained in it.

# **Contents**

1	Intro	oduction	5
	1.1	Identification of specimen	5
	1.2	Sponsor	5
	1.3	Manufacturer	5
	1.4	Test standard	5
	1.5	Reference standard	5
	1.6	Test number	5
	1.7	Test date	6
2	Desc	cription of specimen	6
	2.1	General	6
	2.2	Dimensions	9
	2.3	Orientation	9
	2.4	Conditioning	9
	2.5	Selection, construction and installation of the specimen and the supporting construction	tion 9
3	Docu	umentation	10
4	Equi	pment	10
	4.1	Furnace	10
	4.2	Temperature	11
	4.3	Measurement system	11
5	Amb	ient temperature	11
6	Depa	arture from standard	11
7	Tern	nination of test	11
8	Test	results	12
	8.1	Critical observations	12
	8.2	Furnace temperature	13
	8.3	Furnace severity	13
	8.4	Specimen temperature	13
	8.5	Performance	14
9	Fire-	resistance level (FRL)	15
10	Field	of direct application of test results	15
11	Test	ed by	15
Appe	ndices .		16
	App	endix A – Measurement location	16
	App	endix B – Photographs	18
	App	endix C – Furnace Temperature	24
	App	endix D – Layout and installation drawings	32
	App	endix E – Specimen Drawings	39
	App	endix F – Certificate(s) of Test	40
Refer	ences		46

# Fire-resistance test on retrofit fire collars protecting a plasterboard wall penetrated by services Sponsored Investigation No. FSP 2120

# 1 Introduction

# 1.1 Identification of specimen

The sponsor identified the specimen as SNAP Multi Service Retrofit MS70R fire collars protecting a plasterboard wall penetrated by six services.

# 1.2 Sponsor

IG6 Pty Ltd as trustee for the IG6 IP Trust 3 Skirmish Court Victoria Point QLD 4165 Australia

### 1.3 Manufacturer

Snap Fire Systems Pty Ltd Building A, 1343 Wynnum Road Tingalpa QLD 4173 Australia

#### 1.4 Test standard

Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4-2014, Fire-resistance tests for elements of construction.

Section 10: Service penetrations and control joints

## 1.5 Reference standard

Australian Standard 4072, Components for the protection of openings in fire-resistant separating elements, Part 1 - 2005, Service penetrations and control joints.

### 1.6 Test number

CSIRO Reference test number FS 4997/4541

#### 1.7 Test date

The fire-resistance test was conducted on 29 June 2020.

# 2 Description of specimen

## 2.1 General

The specimen comprised an 1150-mm x 1150-mm x 90-mm thick plasterboard wall system penetrated by six (6) services protected by retro-fitted Snap Fire Systems fire collars

The plasterboard wall was constructed in accordance with Boral Firestop system SB60.1 with an established fire resistance level (FRL) of -/60/60 as detailed in the document titled "Plasterboard Fire and Acoustic Systems Australia", revision UB1231-SYS 12/18, by USG Boral Building Products Pty Ltd. Construction comprised a 64-mm x 0.55-mm steel studs installed at nominally 600-mm centres, lined on each side with a single layer of 13-mm thick Boral Firestop plasterboard sheets. The plasterboard sheeting was screw fixed to the steel studs using  $6g \times 32$ -mm plasterboard screws at nominally 200-mm centres. The wall cavity was filled with a single layer of 50-mm thick Acoustigard 11 insulation.

For the purpose of the test, the penetrations are referenced as Specimen 1, 2, 3, 4, 5 and 6. Documents containing a complete description of each specimen were supplied by the sponsor and are retained on file.

The pipes and electric cables used in the test are stated to be manufactured in accordance with:

- BS 476-4:1970: Fire Tests on Building Materials and Structures Part 4: Non-Combustibility Test for Materials;
- AS1432:2004 Copper tubes for plumbing, gas fitting and drainage applications;
- AS/NZS 1477:2017 PVC pipes and fittings for pressure applications and
- AS/NZS 5000.1:2005 (R2017): Electric cables Polymeric insulated For working voltages up to and including 0.6/1 (1.2) kV

<u>Specimen 1 - SNAP MS70R Multi Services Retrofit fire collars protecting a DN25B copper tube with 19-mm F/R lagging and a thermoplastic-sheathed cable (TPS).</u>

The SNAP Multi Service Retrofit MS70R fire collar comprised a 0.75-mm thick steel casing with a 69-mm inner diameter and a 0.95-mm thick steel base flange with a 162-mm diameter. The 95 mm high collar casing incorporated a 4-mm thick x 90-mm wide x 250-mm long soft Intumesh intumescent wrap lined within the internal circumference of the collar casing. The closing mechanism comprised three stainless steel springs, a nylon fuse link and a 258-mm long x 88-mm wide 316 stainless steel mesh located around the intumescent strip, as shown in drawing titled "SNAP 70 Multi Service Retro", dated 23 September 2019, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the wall in a back-to-back configuration through the collar mounting brackets using three M4 expandable steel anchors.

The penetrating service comprised a 25-mm diameter copper pipe with a wall thickness of 1.1-mm, lagged with 19-mm thick E-flex insulation and a 3-core 2.5-mm<sup>2</sup> TPS cable. The lagged pipe and cable were fitted through the collar's sleeve and penetrated the wall through a 64-mm diameter cut-out hole as shown in drawing titled "Specimen #1 1 inch Copper Tube with 19mm F/R Lagging, 2.5mm<sup>2</sup> 3C TPS Cable & MS70R Collar", dated 10 June 2020, by Snap Fire Systems Pty Ltd.

The lagged pipe and cable projected horizontally 550-mm away from the unexposed face of the wall and approximately 500-mm into the furnace chamber. The lagged pipe and cable were supported at nominally 500-mm from the unexposed face of the plasterboard wall. The copper pipe was left open on the unexposed face and crimped closed on the exposed end.

<u>Specimen 2 - SNAP MS70R Multi Services Retrofit fire collar protecting a nominal 50-mm PVC</u> conduit incorporating two 6-mm<sup>2</sup> 3C+E and two 16-mm<sup>2</sup> 3C+E power cables.

The SNAP Multi Service Retrofit MS70R fire collar comprised a 0.75-mm thick steel casing with a 69-mm inner diameter and a 0.95-mm thick steel base flange with a 162-mm diameter. The 95 mm high collar casing incorporated a 4-mm thick x 90-mm wide x 250-mm long soft Intumesh intumescent wrap lined within the internal circumference of the collar casing. The closing mechanism comprised three stainless steel springs, a nylon fuse link and a 258-mm long x 88-mm wide 316 stainless steel mesh located around the intumescent strip, as shown in drawing titled "SNAP 70 Multi Service Retro", dated 23 September 2019, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the wall in a back-to-back configuration through the collar mounting brackets using three M4 expandable steel anchors.

The penetrating service comprised a 60-mm outside diameter Telstra PVC conduit with a wall thickness of 2.71-mm containing two 6-mm<sup>2</sup> 3-core+E power cables and two 16-mm<sup>2</sup> 3-core+E power cables running through the conduit. All the power cables were manufactured by General Cables.

The PVC conduit and four power cables were fitted through the collar's sleeve and penetrated the wall through a 64-mm diameter cut-out hole as shown in drawing titled "Specimen #2 50 PVC Conduit with 16mm² 3C+E & 6mm² 3C+E Power Cables & MS70R Collar", dated 10 June 2020, by Snap Fire Systems Pty Ltd. The conduit and cables projected horizontally 2000-mm away from the unexposed face of the wall and approximately 500-mm into the furnace chamber. The conduit was supported at nominally 500-mm and 1500-mm from the unexposed face of the plasterboard wall. The conduit was open at the unexposed end and plugged with ceramic fibre (Superwool) on the exposed end.

<u>Specimen 3 - SNAP MS70R Multi Services Retrofit fire collars protecting a bundle of 20 Category 5e network cables.</u>

The SNAP Multi Service Retrofit MS70R fire collar comprised a 0.75-mm thick steel casing with a 69-mm inner diameter and a 0.95-mm thick steel base flange with a 162-mm diameter. The 95 mm high collar casing incorporated a 4-mm thick x 90-mm wide x 250-mm long soft Intumesh intumescent wrap lined within the internal circumference of the collar casing. The closing mechanism comprised three stainless steel springs, a nylon fuse link and a 258-mm long x 88-mm wide 316 stainless steel mesh located around the intumescent strip, as shown in drawing titled "SNAP 70 Multi Service Retro", dated 23 September 2019, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the wall in a back-to-back configuration through the collar mounting brackets using three M4 expandable steel anchors.

The penetrating service comprised a bundle of 20 x 5-mm diameter ADC Krone Category 5e network cables. The cables were fitted through the collar's sleeve and penetrated the wall through a 70-mm diameter cut-out hole as shown in drawing titled "Specimen #3 20% Full of Cat5e Cables & MS70R Collar", dated 10 June 2020, by Snap Fire Systems Pty Ltd.

The cables projected horizontally 550-mm away from the unexposed face of the wall and approximately 500-mm into the furnace chamber. The cables were supported at nominally 500-mm from the unexposed face of the plasterboard wall.

# <u>Specimen 4 - SNAP MS70R Multi Services Retrofit fire collars protecting a bundle of 100 Category</u> 5e network cables.

The SNAP Multi Service Retrofit MS70R fire collar comprised a 0.75-mm thick steel casing with a 69-mm inner diameter and a 0.95-mm thick steel base flange with a 162-mm diameter. The 95 mm high collar casing incorporated a 4-mm thick x 90-mm wide x 250-mm long soft Intumesh intumescent wrap lined within the internal circumference of the collar casing. The closing mechanism comprised three stainless steel springs, a nylon fuse link and a 258-mm long x 88-mm wide 316 stainless steel mesh located around the intumescent strip, as shown in drawing titled "SNAP 70 Multi Service Retro", dated 23 September 2019, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the wall in a back-to-back configuration through the collar mounting brackets using three M4 expandable steel anchors.

The penetrating service comprised a bundle of 100 x 5-mm diameter ADC Krone Category 5e network cables. The cables were fitted through the collar's sleeve and penetrated the wall through a 70-mm diameter cut-out hole as shown in drawing titled "Specimen #4 100% Full of Cat5e Cables & MS70R Collar", dated 10 June 2020, by Snap Fire Systems Pty Ltd.

The cables projected horizontally 550-mm away from the unexposed face of the wall and approximately 500-mm into the furnace chamber. The cables were supported at nominally 500-mm from the unexposed face of the plasterboard wall.

# Specimen 5 - SNAP MS70R Multi Services Retrofit fire collar protecting a ¾-inch and a ¾-inch Pair Coil, a nominal 25-mm PN12 PVC-U pipe and a 2.5-mm<sup>2</sup> 3C+E power cable.

The SNAP Multi Service Retrofit MS70R fire collar comprised a 0.75-mm thick steel casing with a 69-mm inner diameter and a 0.95-mm thick steel base flange with a 162-mm diameter. The 95 mm high collar casing incorporated a 4-mm thick x 90-mm wide x 250-mm long soft Intumesh intumescent wrap lined within the internal circumference of the collar casing. The closing mechanism comprised three stainless steel springs, a nylon fuse link and a 258-mm long x 88-mm wide 316 stainless steel mesh located around the intumescent strip, as shown in drawing titled "SNAP 70 Multi Service Retro", dated 23 September 2019, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the wall in a back-to-back configuration through the collar mounting brackets using three M4 expandable steel anchors.

The penetrating service comprised a ¾-inch and a ¾-inch pair coil, a PN12 PVC-U pipe and a 2.5-mm² 3C+E power cable. The Ardent pair coil comprised two copper pipes having outside diameters of 9.82-mm, 19.05-mm and wall thicknesses of 0.81-mm and 1.14-mm respectively with both pipes covered with a 10-mm thick crosslinked non-fire rated PE foam lagging. The Pipemaster PN12 PVC-U pipe had an outside diameter of 26.82-mm and wall thickness of 1.6-mm. The Electra Cables comprised a 2.5-mm² 3C+E power cable with an outside diameter of 11.1-mm.

The pair coil, PVC pipe and power cable were fitted through the collar's sleeve and penetrated the wall through a through a 64-mm diameter cut-out hole as shown in drawing titled "Specimen #5 %-in lnsulated Copper Pair Coil, 25-mm Pressure PVC, 2.5mm² 3C+E Cable & MS70R", dated 10 June 2020", by Snap Fire Systems Pty Ltd. The annular gap around pair coils, PVC pipe, cable and plasterboard on both sides of the wall was filled with a 10-mm deep bead H.B Fullers Firesound sealant.

The 25-mm PVC conduit projected horizontally 2000-mm away from the unexposed face of the wall and approximately 500 mm into the furnace chamber, and was supported at nominally 500-mm, and 1500-mm from the unexposed face of the wall. The ¾-inch and ¾-inch copper lagged pair coil pipes and the power cable projected horizontally 550-mm away from the unexposed face of the wall and approximately 500 mm into the furnace chamber and were supported at nominally 500-mm from the wall. The 25-mm pressure PVC pipe was open on the unexposed end and plugged with a ceramic fibre (Superwool) plug on the exposed end. The ¾-inch and a ¾-inch copper pipes were left open on the unexposed face and crimped closed on the exposed end.

<u>Specimen 6 - SNAP MS70R Multi Services Retrofit fire collars protecting a bundle of six 16-mm<sup>2</sup></u> 3C+E and three 6-mm<sup>2</sup> 3C+E power cables.

The SNAP Multi Service Retrofit MS70R fire collar comprised a 0.75-mm thick steel casing with a 69-mm inner diameter and a 0.95-mm thick steel base flange with a 162-mm diameter. The 95 mm high collar casing incorporated a 4-mm thick x 90-mm wide x 250-mm long soft Intumesh intumescent wrap lined within the internal circumference of the collar casing. The closing mechanism comprised three stainless steel springs, a nylon fuse link and a 258-mm long x 88-mm wide 316 stainless steel mesh located around the intumescent strip, as shown in drawing titled "SNAP 70 Multi Service Retro", dated 23 September 2019, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the wall in a back-to-back configuration through the collar mounting brackets using three M4 expandable steel anchors.

The penetrating service comprised a bundle of six 16-mm<sup>2</sup> 3-core+E power cables and three 6-mm<sup>2</sup> 3-core+E power cables. All the cables were manufactured by General Cables. The cables were fitted through the collar's sleeve and penetrated the wall through a 70-mm diameter cut-out hole as shown in drawing titled "Specimen #6 16mm<sup>2</sup> 3C+E & 6mm<sup>2</sup> 3C+E Power Cables & MS70R Collar", dated 10 June 2020, by Snap Fire Systems Pty Ltd.

The annular gap around the cables and plasterboard on both sides of the wall was filled with a 10-mm deep bead H.B Fullers Firesound sealant. The cables projected horizontally 550-mm away from the unexposed face of the wall and approximately 500-mm into the furnace chamber. The cables were supported at nominally 500-mm from the unexposed face of the plasterboard wall.

### 2.2 Dimensions

The wall specimen was nominally 1150-mm wide x 1150-mm high x 90-mm thick.

### 2.3 Orientation

The plasterboard wall was placed vertically against the furnace chamber and subjected to fire exposure from one side only.

# 2.4 Conditioning

The specimen was delivered on 22 June 2020 and left under standard laboratory atmospheric conditions until the test date.

# 2.5 Selection, construction and installation of the specimen and the supporting construction

The supporting wall construction and specimen installation was organised by the sponsor. CSIRO was not involved in the selection of the materials.

# 3 Documentation

The following documents were supplied or referenced by the sponsor as a complete description of the specimen and should be read in conjunction with this report:

- Documents titled "Plasterboard Fire and Acoustic Systems Australia", revision UB1231-SYS 12/18, by USG Boral Building Products Pty Ltd.
- Drawing titled "Test Wall W-20-E Layout", dated 10 June 2020, by Snap Fire Systems Pty Ltd.
- Drawing titled "Specimen #1 1 inch Copper Tube with 19mm F/R Lagging, 2.5mm<sup>2</sup> 3C TPS Cable & MS70R Collar", dated 10 June 2020, by Snap Fire Systems Pty Ltd.
- Drawing titled "Specimen #2 50 PVC Conduit with 16mm<sup>2</sup> 3C+E & 6mm<sup>2</sup> 3C+E Power Cables
   MS70R Collar", dated 10 June 2020, by Snap Fire Systems Pty Ltd.
- Drawing titled "Specimen #3 20% Full of Cat5e Cables & MS70R Collar", dated 10 June 2020, provided by Snap Fire Systems Pty Ltd.
- Drawing titled "Specimen #4 100% Full of Cat5e Cables & MS70R Collar", dated 10 June 2020, provided by Snap Fire Systems Pty Ltd.
- Drawing titled "Specimen #5 ¾-in & ¾-in Insulated Copper Pair Coil, 25-mm Pressure PVC, 2.5mm² 3C+ E & MS70R", dated 10 June 2020", provided by Snap Fire Systems Pty Ltd.
- Drawing titled "Specimen #6 16mm² 3C+E & 6mm² 3C+E Power Cables & MS70R Collar", dated 10 June 2020, provided by Snap Fire Systems Pty Ltd.
- Drawing titled "SNAP 50 Multi Service Retro", dated 23 September 2019, by Snap Fire Systems Pty Ltd.

# 4 Equipment

## 4.1 Furnace

The furnace had a nominal opening of 1000-mm x 1000-mm for attachment of vertical or horizontal specimens.

The furnace was lined with refractory bricks and materials with the thermal properties as specified in AS 1530.4-2014 and was heated by combustion of a mixture of natural gas and air.

## 4.2 Temperature

The temperature in the furnace chamber was measured by four type K, 3-mm diameter, and 310 stainless steel Mineral Insulated Metal Sheathed (MIMS) thermocouples. Each thermocouple was housed in high-nickel steel tubes opened at the exposed end.

The temperatures of the specimen were measured by glass-fibre insulated and sheathed K-type thermocouples with a wire diameter of 0.5-mm.

Location of the thermocouples on the unexposed face of the specimen are described in Appendix A. Additional thermocouples were placed on the unexposed cables at 75-mm and 125-mm from the collar of Specimen 6, which were not taken into consideration for the insulation criterion.

# 4.3 Measurement system

The primary measurement system comprised a multiple-channel data logger, scanning at one minute intervals during the test.

# **5** Ambient temperature

The temperature of the test area was 14°C at the commencement of the test.

# 6 Departure from standard

There were no departures from the requirements of AS 1530.4-2014.

# 7 Termination of test

The test was terminated at 91 minutes by the agreement with the sponsor.

# 8 Test results

# 8.1 Critical observations

The following observations were made during the fire-resistance test:

Time	Observation
1 minutes -	Smoke is being emitted between the collar and pipe of Specimens 3, 4 and 6. Smoke has begun fluing from the end of the pipe of Specimen 2. Smoke has begun fluing from the end of the pipe of Specimen 1. The bundle of cables of Specimen 3 has been pushed out away from the wall approximately 30-mm.
5 minutes -	The level of smoke emitted from Specimen 6 has increased.
6 minutes -	Smoke has ceased fluing from the collars of Specimens 3 and 4.
7 minutes -	Smoke has ceased fluing from the collar of Specimen 6.
9 minutes -	Smoke has ceased fluing from the collar of Specimen 2.
10 minutes -	Light smoke has resumed fluing between the collar and pipe of Specimen 3.
	Smoke has ceased fluing from Specimen 1.
11 minutes -	The bundle of cables of Specimen 3 has been pushed back to their original position.
21 minutes -	Visible staining is noted on the pair coil and PVC pipe of Specimen 5.
23 minutes -	Smoke has resumed fluing between the collar and pipe of Specimen 4 with visible discolouration on the top of the cables adjacent to the collar.
26 minutes -	The E-flex insulation around the pipe of Specimen 1 has swollen along the length of the pipe and split adjacent to thermocouples #6 and #7.
28 minutes -	The blue sheath at the top of cable bundles of Specimens 3 and 4 have started to discolour, with the adjacent collars having smoke stains (Photograph 5).
30 minutes -	The level of smoke fluing between the collar and pipe of specimens 3, 4, and 6 has increased.
35 minutes -	The level of smoke fluing between the collar and pipe of Specimens 3, 4 has decreased.
40 minutes -	Light smoke has resumed fluing between the collar and pipe of Specimens 5 and 6
45 minutes -	The lagging of the pair coil has begun to melt and shrink with thermocouple #32 on the lagging around the ¾ inch copper pipe no longer in full contact. Roving thermocouple was applied to the lagging around the ¾ inch copper pipe 25-mm from the collar, a temperature of 53°C was noted at this time.
52 minutes -	The orange sheath on the 16-mm <sup>2</sup> cable – top right of Specimen 6 adjacent to the collar has begun to split (Photograph 8).
59 minutes -	Roving thermocouple applied to the lagging around the ¾ inch copper pipe 25-mm from the collar, a temperature of 126°C was noted at this time.
62 minutes -	Smoke has resumed fluing from the end of the pipe of Specimen 1.
65 minutes -	The orange sheath on the 16-mm <sup>2</sup> cable – top right of Specimen 6 adjacent to the collar continues to split.
73 minutes -	A loud clicking noise was heard from the specimen, the nylon fuse inside the collar of Specimen 4 on the unexposed face has been released, however, the two lower nylon fuses remain attached to the casing.

74 minutes - The plasterboard wall around Specimens 2 and 4 has begun to discolour and char.

77 minutes - <u>Insulation failure of Specimen 2</u> – maximum temperature rise of 180K is exceeded on the right side of collar 25-mm from the wall.

78 minutes - <u>Insulation failure of Specimen 1</u> – maximum temperature rise of 180K is exceeded on the plasterboard wall 25-mm above the collar.

79 minutes - <u>Insulation failure of Specimen 3</u> – maximum temperature rise of 180K is exceeded on the plasterboard wall 25-mm above the collar.

80 minutes - <u>Insulation failure of Specimen 4</u> – maximum temperature rise of 180K is exceeded on the plasterboard wall 25-mm above the collar.

The plasterboard wall continues to char.

81 minutes - A dark liquid is dropping down the wall below Specimen 4.

83 minutes - Insulation failure of Specimen 5 – maximum temperature rise of 180K is exceeded on the plasterboard wall 25-mm above the collar.

The plasterboard wall continues to char around specimens.

87 minutes - Roving thermocouple applied to the lagging of the ¾ inch copper pipe of Specimen 5, 25-mm from the collar with a temperature of 247°C noted at this time

91 minutes - Test terminated.

# 8.2 Furnace temperature

Figure 1 shows the standard curves of temperature versus time for heating the furnace chamber and the actual curves of average and maximum temperature versus time recorded during the heating period.

# 8.3 Furnace severity

Figure 2 shows the curve of furnace severity versus time during the heating period.

# 8.4 Specimen temperature

Figure 3 shows the curve of temperature versus time associated with Specimen 1.

Figure 4 shows the curve of temperature versus time associated with Specimen 2.

Figure 5 shows the curve of temperature versus time associated with Specimen 3.

Figure 6 shows the curve of temperature versus time associated with Specimen 4.

Figure 7 shows the curve of temperature versus time associated with Specimen 5.

Figure 8 shows the curve of temperature versus time associated with Specimen 6.

## 8.5 Performance

Performance observed in respect of the following AS 1530.4-2014 criteria:

<u>Specimen 1 - SNAP MS70R Multi Services Retrofit fire collars protecting a DN25B copper tube with 19-mm F/R lagging and a thermoplastic-sheathed cable (TPS)</u>

Structural adequacy - not applicable
Integrity - no failure at 91 minutes
Insulation - 78 minutes

<u>Specimen 2 - SNAP MS70R Multi Services Retrofit fire collar protecting a nominal 50-mm PVC conduit incorporating two 6-mm<sup>2</sup> 3C+E and two 16-mm<sup>2</sup> 3C+E power cables</u>

Structural adequacy - not applicable
Integrity - no failure at 91 minutes
Insulation - 77 minutes

<u>Specimen 3 - SNAP MS70R Multi Services Retrofit fire collars protecting a bundle of 20 Category 5e network cables</u>

Structural adequacy - not applicable
Integrity - no failure at 91 minutes
Insulation - 79 minutes

<u>Specimen 4 - SNAP MS70R Multi Services Retrofit fire collars protecting a bundle of 100 Category 5e network cables</u>

Structural adequacy - not applicable Integrity - no failure at 91 minutes Insulation - 80 minutes

Specimen 5 - SNAP MS70R Multi Services Retrofit fire collar protecting a ¾-inch and a ¾-inch Pair Coil, a nominal 25-mm PN12 PVC-U pipe and a 2.5-mm² 3C+E power cable

Structural adequacy - not applicable
Integrity - no failure at 91 minutes
Insulation - 83 minutes

<u>Specimen 6 - SNAP MS70R Multi Services Retrofit fire collars protecting a bundle of six 16-mm<sup>2</sup> 3C+E and three 6-mm<sup>2</sup> 3C+E power cables</u>

Structural adequacy - not applicable
Integrity - no failure at 91 minutes
Insulation - no failure at 91 minutes

This report details methods of construction, the test conditions and the results obtained when the specific element of construction described herein was tested following the procedure outlined in AS 1530.4. Any significant variation with respect to size, constructional details, loads, stresses, edge or end conditions, other than those allowed under the field of direct application in the relevant test method, is not covered by this report.

Because of the nature of fire resistance testing and the consequent difficulty in quantifying the uncertainty of measurement of fire resistance, it is not possible to provide a stated degree of accuracy of the result.

# 9 Fire-resistance level (FRL)

For the purpose of building regulations in Australia, the FRL's of the test specimens were as follows:

Specimen 1 -/60/60

Specimen 2 -/60/60

Specimen 3 -/60/60

Specimen 4 -/60/60

Specimen 5 -/60/60

Specimen 6 -/60/60

The fire-resistance level is applicable when the system is exposed to fire from either direction.

The test was conducted on a wall system with an established FRL of -/60/60. The maximum FRL of any test specimen cannot exceed the FRL achieved by the wall system in which it was installed.

For the purposes of AS 1530.4-2014 the results of these fire tests may be used to directly assess fire hazard, but it should be noted that a single test method will not provide a full assessment of fire hazard under all fire conditions.

# 10 Field of direct application of test results

The results of the fire test contained in this test report are directly applicable, without reference to the testing authority, to similar constructions where one or more changes listed in Clause 10.12 of AS 1530.4-2014, have been made provided no individual component is removed or reduced.

# 11 Tested by

Peter Gordon Testing Officer


# **Appendices**

# Appendix A – Measurement location


SPECIMEN	T/C Position	T/C designation
	On plasterboard wall, 25-mm above collar	S1
Specimen 1 - SNAP MS70R Multi	On plasterboard wall, 25-mm below collar	S2
Services Retrofit fire collars	On collar top side	S3
protecting a 1-inch copper pipe with Thermotec E-flex ST FRV and	On collar left side	S4
a thermoplastic-sheathed (TPS)	On TPS cable, 25-mm from collar	S5
cable.	On top of lagging, 25-mm from collar	S6
	On right side of lagging, 25-mm from collar	S7
	On plasterboard wall, 25-mm above collar	S8
<b>Specimen 2</b> - SNAP MS70R Multi Services Retrofit fire collar	On plasterboard wall, 25-mm left of collar	S9
protecting a nominal 50-mm PVC	On collar top right side	S10
conduit incorporating two 16-mm <sup>2</sup> 3C+E and two 6-mm <sup>2</sup>	On collar left side	S11
3C+E power cables.	On top of pipe, 25-mm from collar	S12
	On left of pipe, 25-mm from collar	S13
	On plasterboard wall, 25-mm from collar left	S14
Specimen 3 - SNAP MS70R Multi	On plasterboard wall, 25-mm below collar	S15
Services Retrofit fire collars	On collar left side	S16
protecting a bundle of 20 Category 5e network cables.	On collar bottom side	S17
	On top of cables, 25-mm from collar	S18
	On bottom of cables, 25-mm from collar	S19
	On plasterboard wall, 25-mm above collar	S20
Specimen 4 SNAD MC70P Multi	On plasterboard wall, 25-mm below collar	S21
<b>Specimen 4</b> - SNAP MS70R Multi Services Retrofit fire collars	On collar top side	S22
protecting a bundle of 100 Category 5e network cables.	On collar bottom side	S23
Category De Hetwork Cables.	On top of cables, 25-mm from collar	S24
	On bottom of cables, 25-mm from collar	S25

SPECIMEN	T/C Position	T/C designation
	On Plasterboard wall, 25-mm above collar	S26
	On Plasterboard wall, 25-mm below collar	S27
<b>Specimen 5</b> - SNAP MS70R Multi Services Retrofit fire collar	On collar left side	S28
protecting a %-inch and a %-inch	On collar right side	S29
Pair Coils, a nominal 25-mm	On PVC pipe, 25-mm from collar	\$30
pressure PN12 PVC-U pipe and a 2.5-mm <sup>2</sup> 3C+E power cable.	On %-in pipe lagging, 25-mm from collar	S31
	On ¾-in pipe lagging, 25-mm from collar	S32
	On power cable, 25-mm from collar	S33
	On Plasterboard wall, 25-mm above collar	S34
<b>Specimen 6</b> - SNAP MS70R Multi Services Retrofit fire collars protecting a bundle six 16-mm <sup>2</sup> 3C+E and three 6-mm <sup>2</sup> 3C+E power cables.	On Plasterboard wall, 25-mm below collar	S35
	On collar left side	S36
	On collar right side	S37
	On 16-mm² cable, 25-mm from collar	S38
	On 6-mm² cable, 25-mm from collar	S39
	On 16-mm² cable, 75-mm from collar	S40
Additional thermocouples place on the cables of Specimen 6.	On 6-mm² cable, 75-mm from collar	S41
	On 16-mm² cable, 125-mm from collar	S42
	On 6-mm <sup>2</sup> cable, 125-mm from collar	S43
Rover		S44
Ambient		S45


# Appendix B – Photographs




PHOTOGRAPH 1 – EXPOSED FACE OF SPECIMENS PRIOR TO TESTING




PHOTOGRAPH 2 – UNEXPOSED FACE OF SPECIMENS PRIOR TO TESTING




PHOTOGRAPH 3 – SPECIMENS AFTER 2 MINUTES OF TESTING



PHOTOGRAPH 4 – SPECIMENS AFTER 8 MINUTES OF TESTING




PHOTOGRAPH 5 – SPECIMEN 4 AFTER 28 MINUTES OF TESTING




PHOTOGRAPH 6 - SPECIMENS AFTER 30 MINUTES OF TESTING



PHOTOGRAPH 7 – SPECIMENS 5 AND 4 AFTER 45 MINUTES OF TESTING



PHOTOGRAPH 8 – SPECIMEN 6 AFTER 52 MINUTES OF TESTING




PHOTOGRAPH 9 – SPECIMENS AFTER 60 MINUTES OF TESTING



PHOTOGRAPH 10 – SPECIMENS AFTER 74 MINUTES OF TESTING



PHOTOGRAPH 11 – SPECIMENS AFTER 90 MINUTES OF TESTING



PHOTOGRAPH 12 - EXPOSED FACE OF SPECIMENS AT CONCLUSION OF TESTING

# Appendix C – Furnace Temperature





FIGURE 1 – FURNACE TEMPERATURE



**FIGURE 2 – FURNACE SEVERITY** 




FIGURE 3 - TEMPERATURE VERSUS TIME ASSOCIATED WITH SPECIMEN #1




FIGURE 4 - TEMPERATURE VERSUS TIME ASSOCIATED WITH SPECIMEN #2




FIGURE 5 - TEMPERATURE VERSUS TIME ASSOCIATED WITH SPECIMEN #3




FIGURE 6 - TEMPERATURE VERSUS TIME ASSOCIATED WITH SPECIMEN #4




FIGURE 7 - TEMPERATURE VERSUS TIME ASSOCIATED WITH SPECIMEN #5





FIGURE 8 - TEMPERATURE VERSUS TIME ASSOCIATED WITH SPECIMEN #6

# Appendix D – Layout and installation drawings

# Snap Fire Systems Pty Ltd Test Wall W-20-E Layout

Date: 10 JUN 2020




Penetration	Collar Code	Pipe Type	Pipe Diameter
1	MS70R	Copper Tube with F/R lagging and TPS cable	1in(19mm Lagging) & 2.5mm² 3C
2	MS70R	Medium Duty PVC Conduit with Orange Power Cables	50, 2x(16mm² 3C+E) & 2x(6mm² 3C+E)
3	MS70R	20xCat5e Cables	
4	MS70R	100xCat5e Cables	
5	MS70R	Copper pair coil lagged in non-F/R lagging, 3 core+E round power cable and pressure PVC	%&¾in (9mm Lagging), 2.5mm² 3C+E, 25mm
6	MS70R	Orange Power Cables	3x(6mm² 3C+E) & 6x(16mm² 3C+E)

DRAWING TITLED "TEST WALL W-20-E LAYOUT, DATED 10 JUNE 2020, PROVIDED BY SNAP FIRE SYSTEMS PTY LTD.

Specimen #1

1inch Copper Tube with 19mm F/R Lagging, 2.5mm<sup>2</sup> 3C TPS Cable & MS70R Collar

Date: 10 JUN 2020




DRAWING TITLED "1 INCH COPPER TUBE WITH 19MM F/R LAGGING, 2.5MM<sup>2</sup> 3C TPS CABLE & MS70R COLLAR", DATED 10 JUNE 2020, PROVIDED BY SNAP FIRE SYSTEMS PTY LTD


Specimen #2

50 PVC Conduit with 16mm<sup>2</sup> 3C+E & 6mm<sup>2</sup> 3C+E Power Cables & MS70R Collar

Date: 10 JUN 2020




Specimen #3
20% Full of Cat5e Cables & MS70R Collar
Date: 10 JUN 2020



DRAWING TITLED "SPECIMEN #3 20% FULL OF CAT5E CABLES & MS70R COLLAR", DATED 10 JUNE 2020, PROVIDED BY SNAP FIRE SYSTEMS PTY LTD, PROVIDED BY SNAP FIRE SYSTEMS PTY LTD

Specimen #4
100% Full of Cat5e Cables & MS70R Collar

Date: 10 JUN 2020




DRAWING TITLED "SPECIMEN #4 100% FULL OF CATSE CABLES & MS70R COLLAR", DATED 10 JUNE 2020, PROVIDED BY SNAP FIRE SYSTEMS PTY LTD, PROVIDED BY SNAP FIRE SYSTEMS PTY LTD

Specimen #5

3/4-in & 3/8-in Insulated Copper Pair Coil, 25mm Pressure PVC, 2.5mm² 3C+E Cable & MS70R


Date: 10 JUN 2020



DRAWING TITLED "SPECIMEN #5 ¾-IN & ¾-IN INSULATED COPPER PAIR COIL, 25-MM PRESSURE PVC, 2.5MM² 3C+ E & MS70R", DATED 10 JUNE 2020, PROVIDED BY SNAP FIRE SYSTEMS PTY LTD


Specimen #6

16mm<sup>2</sup> 3C+E & 6mm<sup>2</sup> 3C+E Power Cables & MS70R Collar Date: 10 JUN 2020



DRAWING TITLED "SPECIMEN #6 16MM<sup>2</sup> 3C+E & 6MM<sup>2</sup> 3C+E POWER CABLES & MS70R COLLAR", DATED 10 JUNE 2020, PROVIDED BY SNAP FIRE SYSTEMS PTY LTD

# Appendix E – Specimen Drawings



DRAWING TITLED "SNAP 50 MULTI SERVICE RETRO", DATED 23 SEPTEMBER 2019, BY SNAP FIRE SYSTEMS.

# Appendix F – Certificate(s) of Test

#### **INFRASTRUCTURE TECHNOLOGIES**

www.csiro.au

14 Julius Avenue, North Ryde NSW 2113
PO Box 52, North Ryde NSW 1670, Australia
T (02) 9490 5444 • ABN 41 687 119 230



# Certificate of Test

No. 3479

This is to certify that the element of construction described below was tested by CSIRO Infrastructure Technologies in accordance with Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4 Fire-resistance tests of elements of construction, 2014, Section 10: Service penetrations and control joints, on behalf of:

IG6 Pty Ltd as trustee for the IG6 IP Trust

3 Skirmish Court Victoria Point Qld 4165

A full description of the test specimen and the complete test results are detailed in the Division's report numbered FSP 2120.

Product Name: SNAP MS70R Multi Services Retrofit fire collars protecting a DN25B copper tube with 19-mm F/R lagging and a

thermoplastic-sheathed cable (TPS) (Specimen 1)

Description:

The specimen comprised an 1150-mm x 1150-mm x 90-mm thick plasterboard wall system penetrated by a service protected by retro-fitted Snap Fire Systems fire collars. The plasterboard wall was constructed in accordance with Boral Firestop system SB60.1 with an established fire resistance level (FRL) of -/60/60 as detailed in the document titled "Plasterboard Fire and Acoustic Systems Australia", revision UB1231-SYS 12/18, by USG Boral Building Products Pty Ltd. The SNAP Multi Service Retrofit MS70R fire collar comprised a 0.75-mm thick steel casing with a 69-mm inner diameter and a 0.95-mm thick steel base flange with a 162-mm diameter as shown in drawing titled "SNAP 70 Multi Service Retro", dated 23 September 2019, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the wall in a back-to-back configuration through the collar mounting brackets using three M4 expandable steel anchors. The penetrating service comprised a 25-mm diameter copper pipe with a wall thickness of 1.1 mm, lagged with 19-mm thick E-flex insulation and a 3-core 2.5 mm2 TPS cable as shown in drawing titled "Specimen #1 1 inch Copper Tube with 19mm F/R Lagging, 2.5mm² 3C TPS Cable & MS70R Collar", dated 10 June 2020, by Snap Fire Systems Pty Ltd. The lagged pipe and cable projected horizontally 550-mm away from the unexposed face of the wall and approximately 500 mm into the furnace chamber. The lagged pipe and cable were supported at nominally 500 mm from the unexposed face of the plasterboard wall. The copper pipe was left open on the unexposed face and crimped closed on the exposed end.

Performance observed in respect of the following AS 1530.4-2014 criteria

Structural Adequacy - not applicable
Integrity - no failure at 91 minutes
Insulation - 78 minutes

and therefore for the purpose of Building Regulations in Australia, achieved a fire-resistance level (FRL) of -/60/60.

The fire-resistance level (FRL) of the specimen is applicable when the system is exposed to fire from either direction. The maximum FRL of any test specimen cannot exceed the FRL achieved by the system in which it was installed. For the purposes of AS 1530.4-2014 the results of these fire tests may be used to directly assess fire hazard, but it should be noted that a single test method will not provide a full assessment of fire hazard under all fire conditions. This certificate is provided for general information only and does not comply with regulatory requirements for evidence of compliance.

Testing Officer: Peter Gordon Date of Test: 29 June 2020

Issued on the 7<sup>th</sup> day of September 2020 without alterations or additions.

B. Rong

Brett Roddy | Manager, Fire Testing and Assessments

"Copyright CSIRO 2020 ©"
Copying or alteration of this report without written authorisation from CSIRO is forbidden



This document is issued in accordance with NATA's accreditation requirements.

Accreditation No. 165 – Corporate Site No. 3625

Accredited for compliance with ISO/IEC 17025 - Testing

www.csiro.au

14 Julius Avenue, North Ryde NSW 2113 PO Box 52, North Ryde NSW 1670, Australia T (02) 9490 5444 • ABN 41 687 119 230



# Certificate of Test

No. 3480

This is to certify that the element of construction described below was tested by CSIRO Infrastructure Technologies in accordance with Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4 Fire-resistance tests of elements of construction, 2014, Section 10: Service penetrations and control joints, on behalf of:

IG6 Pty Ltd as trustee for the IG6 IP Trust

3 Skirmish Court Victoria Point Qld 4165

A full description of the test specimen and the complete test results are detailed in the Division's report numbered FSP 2120.

Product Name: SNAP MS70R Multi Services Retrofit fire collar protecting a nominal 50-mm PVC conduit incorporating two

6-mm2 3C+E and two 16-mm2 3C+E power cables (Specimen 2)

Description:

The specimen comprised an 1150-mm x 1150-mm x 90-mm thick plasterboard wall system penetrated by a service protected by retro-fitted Snap Fire Systems fire collars. The plasterboard wall was constructed in accordance with Boral Firestop system SB60.1 with an established fire resistance level (FRL) of -/60/60 as detailed in the document titled "Plasterboard Fire and Acoustic Systems Australia", revision UB1231-SYS 12/18, by USG Boral Building Products Pty Ltd. The SNAP Multi Service Retrofit MS70R fire collar comprised a 0.75-mm thick steel casing with a 69-mm inner diameter and a 0.95-mm thick steel base flange with a 162-mm diameter as shown in drawing titled "SNAP 70 Multi Service Retro", dated 23 September 2019, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the wall in a back-to-back configuration through the collar mounting brackets using three M4 expandable steel anchors. The penetrating service comprised a 60-mm outside diameter Telstra PVC conduit with a wall thickness of 2.71-mm containing two 6-mm2 3-core+E power cables and two 16-mm2 3 core+E power cables running through the conduit as shown in drawing titled "Specimen #2 50 PVC Conduit with 16mm² 3C+E & 6mm² 3C+E Power Cables & MS70R Collar", dated 10 June 2020, by Snap Fire Systems Pty Ltd. The conduit and cables projected horizontally 2000-mm away from the unexposed face of the wall and approximately 500 mm into the furnace chamber. The conduit was supported at nominally 500 mm and 1500 mm from the unexposed face of the plasterboard wall. The conduit was open at the unexposed end and plugged with ceramic fibre (Superwool) on the exposed end.

Performance observed in respect of the following AS 1530.4-2014 criteria

Structural Adequacy - not applicable Integrity - no failure at 91 minutes Insulation - 77 minutes

and therefore for the purpose of Building Regulations in Australia, achieved a fire-resistance level (FRL) of -/60/60.

The fire-resistance level (FRL) of the specimen is applicable when the system is exposed to fire from either direction. The maximum FRL of any test specimen cannot exceed the FRL achieved by the system in which it was installed. For the purposes of AS 1530.4-2014 the results of these fire tests may be used to directly assess fire hazard, but it should be noted that a single test method will not provide a full assessment of fire hazard under all fire conditions. This certificate is provided for general information only and does not comply with regulatory requirements for evidence of compliance.

Testing Officer: Peter Gordon Date of Test: 29 June 2020

Issued on the 7<sup>th</sup> day of September 2020 without alterations or additions.

Brett Roddy | Manager, Fire Testing and Assessments

"Copyright CSIRO 2020  $\mathbb{Q}$ "
Copying or alteration of this report without written authorisation from CSIRO is forbidden



This document is issued in accordance with NATA's accreditation requirements.

Accreditation No. 165 – Corporate Site No. 3625

Accredited for compliance with ISO/IEC 17025 - Testing

www.csiro.au

14 Julius Avenue, North Ryde NSW 2113 PO Box 52, North Ryde NSW 1670, Australia T (02) 9490 5444 • ABN 41 687 119 230



# Certificate of Test

No. 3481

This is to certify that the element of construction described below was tested by CSIRO Infrastructure Technologies in accordance with Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4 Fire-resistance tests of elements of construction, 2014, Section 10: Service penetrations and control joints, on behalf of:

IG6 Pty Ltd as trustee for the IG6 IP Trust

3 Skirmish Court

Victoria Point Qld 4165

A full description of the test specimen and the complete test results are detailed in the Division's report numbered FSP 2120.

Product Name: SNAP MS70R Multi Services Retrofit fire collars protecting a bundle of 20 Category 5e network cables

(Specimen 3)

Description:

The specimen comprised an 1150-mm x 1150-mm x 90-mm thick plasterboard wall system penetrated by a service protected by retro-fitted Snap Fire Systems fire collars. The plasterboard wall was constructed in accordance with Boral Firestop system SB60.1 with an established fire resistance level (FRL) of -/60/60 as detailed in the document titled "Plasterboard Fire and Acoustic Systems Australia", revision UB1231-SYS 12/18, by USG Boral Building Products Pty Ltd. The SNAP Multi Service Retrofit MS70R fire collar comprised a 0.75-mm thick steel casing with a 69-mm inner diameter and a 0.95-mm thick steel base flange with a 162-mm diameter as shown in drawing titled "SNAP 70 Multi Service Retro", dated 23 September 2019, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the wall in a back-to-back configuration through the collar mounting brackets using three M4 expandable steel anchors. The penetrating service comprised a bundle of 20 x 5-mm diameter ADC Krone Category 5e network cables as shown in drawing titled "Specimen #3 20% Full of Cat5e Cables & MS70R Collar", dated 10 June 2020, by Snap Fire Systems Pty Ltd. The cables projected horizontally 550 mm away from the unexposed face of the wall and approximately 500 mm into the furnace chamber. The cables were supported at nominally 500-mm from the unexposed face of the plasterboard wall.

Performance observed in respect of the following AS 1530.4-2014 criteria

Structural Adequacy - not applicable
Integrity - no failure at 91 minutes
Insulation - 79 minutes

and therefore for the purpose of Building Regulations in Australia, achieved a fire-resistance level (FRL) of -/60/60.

The fire-resistance level (FRL) of the specimen is applicable when the system is exposed to fire from either direction. The maximum FRL of any test specimen cannot exceed the FRL achieved by the system in which it was installed. For the purposes of AS 1530.4-2014 the results of these fire tests may be used to directly assess fire hazard, but it should be noted that a single test method will not provide a full assessment of fire hazard under all fire conditions. This certificate is provided for general information only and does not comply with regulatory requirements for evidence of compliance.

Testing Officer: Peter Gordon Date of Test: 29 June 2020

Issued on the 7<sup>th</sup> day of September 2020 without alterations or additions.

B. Rong

Brett Roddy | Manager, Fire Testing and Assessments

"Copyright CSIRO 2020  $\mathbb{Q}$ "
Copying or alteration of this report without written authorisation from CSIRO is forbidden



This document is issued in accordance with NATA's accreditation requirements.

Accreditation No. 165 – Corporate Site No. 3625

Accredited for compliance with ISO/IEC 17025 - Testing

www.csiro.au

14 Julius Avenue, North Ryde NSW 2113 PO Box 52, North Ryde NSW 1670, Australia T (02) 9490 5444 • ABN 41 687 119 230



# Certificate of Test

No. 3482

This is to certify that the element of construction described below was tested by CSIRO Infrastructure Technologies in accordance with Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4 Fire-resistance tests of elements of construction, 2014, Section 10: Service penetrations and control joints, on behalf of:

IG6 Pty Ltd as trustee for the IG6 IP Trust

3 Skirmish Court

Victoria Point Qld 4165

A full description of the test specimen and the complete test results are detailed in the Division's report numbered FSP 2120.

Product Name: SNAP MS70R Multi Services Retrofit fire collars protecting a bundle of 100 Category 5e network cables

Specimen 4)

Description:

The specimen comprised an 1150-mm x 1150-mm x 90-mm thick plasterboard wall system penetrated by a service protected by retro-fitted Snap Fire Systems fire collars. The plasterboard wall was constructed in accordance with Boral Firestop system SB60.1 with an established fire resistance level (FRL) of -/60/60 as detailed in the document titled "Plasterboard Fire and Acoustic Systems Australia", revision UB1231-SYS 12/18, by USG Boral Building Products Pty Ltd. The SNAP Multi Service Retrofit MS70R fire collar comprised a 0.75-mm thick steel casing with a 69-mm inner diameter and a 0.95-mm thick steel base flange with a 162-mm diameter as shown in drawing titled "SNAP 70 Multi Service Retro", dated 23 September 2019, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the wall in a back-to-back configuration through the collar mounting brackets using three M4 expandable steel anchors. The penetrating service comprised a bundle of 100 x 5-mm diameter ADC Krone Category 5e network cables as shown in drawing titled "Specimen #4 100% Full of Cat5e Cables & MS70R Collar", dated 10 June 2020, by Snap Fire Systems Pty Ltd. The cables projected horizontally 550 mm away from the unexposed face of the wall and approximately 500 mm into the furnace chamber. The cables were supported at nominally 500 mm from the unexposed face of the plasterboard wall.

Performance observed in respect of the following AS 1530.4-2014 criteria

Structural Adequacy - not applicable
Integrity - no failure at 91 minutes
Insulation - 80 minutes

and therefore for the purpose of Building Regulations in Australia, achieved a fire-resistance level (FRL) of -/60/60.

The fire-resistance level (FRL) of the specimen is applicable when the system is exposed to fire from either direction. The maximum FRL of any test specimen cannot exceed the FRL achieved by the system in which it was installed. For the purposes of AS 1530.4-2014 the results of these fire tests may be used to directly assess fire hazard, but it should be noted that a single test method will not provide a full assessment of fire hazard under all fire conditions. This certificate is provided for general information only and does not comply with regulatory requirements for evidence of compliance.

Testing Officer: Peter Gordon Date of Test: 29 June 2020

Issued on the 7<sup>th</sup> day of September 2020 without alterations or additions.

B. Roug

Brett Roddy | Manager, Fire Testing and Assessments

"Соругіght CSIRO 2020  $\mathbb{Q}$ "
Соругіg or alteration of this report without written authorisation from CSIRO is forbidden



This document is issued in accordance with NATA's accreditation requirements.

Accreditation No. 165 – Corporate Site No. 3625

Accredited for compliance with ISO/IEC 17025 - Testing

www.csiro.au

14 Julius Avenue, North Ryde NSW 2113 PO Box 52, North Ryde NSW 1670, Australia T (02) 9490 5444 • ABN 41 687 119 230



# Certificate of Test

No. 3483

This is to certify that the element of construction described below was tested by CSIRO Infrastructure Technologies in accordance with Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4 Fire-resistance tests of elements of construction, 2014, Section 10: Service penetrations and control joints, on behalf of:

IG6 Pty Ltd as trustee for the IG6 IP Trust

3 Skirmish Court Victoria Point Qld 4165

A full description of the test specimen and the complete test results are detailed in the Division's report numbered FSP 2120.

Product Name: SNAP MS70R Multi Services Retrofit fire collar protecting a %-inch and a %-inch Pair Coil, a nominal 25-mm PN12

PVC-U pipe and a 2.5-mm2 3C+E power cable (Specimen 5)

Description:

The specimen comprised an 1150-mm x 1150-mm x 90-mm thick plasterboard wall system penetrated by a service protected by retro-fitted Snap Fire Systems fire collars. The plasterboard wall was constructed in accordance with Boral Firestop system SB60.1 with an established fire resistance level (FRL) of -/60/60 as detailed in the document titled "Plasterboard Fire and Acoustic Systems Australia", revision UB1231-SYS 12/18, by USG Boral Building Products Pty Ltd. The SNAP Multi Service Retrofit MS70R fire collar comprised a 0.75-mm thick steel casing with a 69-mm inner diameter and a 0.95-mm thick steel base flange with a 162-mm diameter as shown in drawing titled "SNAP 70 Multi Service Retro", dated 23 September 2019, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the wall in a back-to-back configuration through the collar mounting brackets using three M4 expandable steel anchors. The penetrating service comprised a ½-inch and a ½-inch pair coil, a PN12 PVC-U pipe and a 2.5 mm2 3C+E power cable as shown in drawing titled "Specimen #5 1/4-in & 1/3-in Insulated Copper Pair Coil, 25-mm Pressure PVC, 2.5mm2 3C+E Cable & MS70R", dated 10 June 2020", by Snap Fire Systems Pty Ltd. The 25-mm PVC conduit projected horizontally 2000-mm away from the unexposed face of the wall and approximately 500 mm into the furnace chamber, and was supported at nominally 500 mm, and 1500-mm from the unexposed face of the wall. The %-inch and %-inch copper lagged pair coil pipes and the power cable projected horizontally 550-mm away from the unexposed face of the wall and approximately 500 mm into the furnace chamber and were supported at nominally 500-mm from the wall. The 25-mm pressure PVC pipe was open on the unexposed end and plugged with a ceramic fibre (Superwool) plug on the exposed end. The %-inch and a %-inch copper pipes were left open on unexposed face and crimped closed on the exposed end.

Performance observed in respect of the following AS 1530.4-2014 criteria

Structural Adequacy - not applicable Integrity - no failure at 91 minutes Insulation - 83 minutes

and therefore for the purpose of Building Regulations in Australia, achieved a fire-resistance level (FRL) of -/60/60.

The fire-resistance level (FRL) of the specimen is applicable when the system is exposed to fire from either direction. The maximum FRL of any test specimen cannot exceed the FRL achieved by the system in which it was installed. For the purposes of AS 1530.4-2014 the results of these fire tests may be used to directly assess fire hazard, but it should be noted that a single test method will not provide a full assessment of fire hazard under all fire conditions. This certificate is provided for general information only and does not comply with regulatory requirements for evidence of compliance.

Testing Officer: Peter Gordon Date of Test: 29 June 2020

Issued on the  $7^{\text{th}}$  day of September 2020 without alterations or additions.

Brett Roddy | Manager, Fire Testing and Assessments

"Copyright CSIRO 2020  $\mathbb{Q}$ "
Copyring or alteration of this report without written authorisation from CSIRO is forbidden



B. Rong

This document is issued in accordance with NATA's accreditation requirements.

Accreditation No. 165 – Corporate Site No. 3625

Accredited for compliance with ISO/IEC 17025 - Testing

www.csiro.au

14 Julius Avenue, North Ryde NSW 2113 PO Box 52, North Ryde NSW 1670, Australia T (02) 9490 5444 • ABN 41 687 119 230



# Certificate of Test

No. 3484

This is to certify that the element of construction described below was tested by CSIRO Infrastructure Technologies in accordance with Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4 Fire-resistance tests of elements of construction, 2014, Section 10: Service penetrations and control joints, on behalf of:

IG6 Pty Ltd as trustee for the IG6 IP Trust

3 Skirmish Court Victoria Point Qld 4165

A full description of the test specimen and the complete test results are detailed in the Division's report numbered FSP 2120.

Product Name: SNAP MS70R Multi Services Retrofit fire collars protecting a bundle of six 16-mm2 3C+E and three 6-mm2 3C+E

power cables (Specimen 6)

Description:

The specimen comprised an 1150-mm x 1150-mm x 90-mm thick plasterboard wall system penetrated by a service protected by retro-fitted Snap Fire Systems fire collars. The plasterboard wall was constructed in accordance with Boral Firestop system SB60.1 with an established fire resistance level (FRL) of -/60/60 as detailed in the document titled "Plasterboard Fire and Acoustic Systems Australia", revision UB1231-SYS 12/18, by USG Boral Building Products Pty Ltd. The SNAP Multi Service Retrofit MS70R fire collar comprised a 0.75-mm thick steel casing with a 69-mm inner diameter and a 0.95-mm thick steel base flange with a 162-mm diameter as shown in drawing titled "SNAP 70 Multi Service Retro", dated 23 September 2019, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the wall in a back-to-back configuration through the collar mounting brackets using three M4 expandable steel anchors. The penetrating service comprised a bundle of six 16-mm² 3-core+E power cables and three 6mm² 3-core+E power cables as shown in drawing titled "Specimen #6 16mm² 3C+E & 6mm² 3C+E Power Cables & MS70R Collar", dated 10 June 2020, by Snap Fire Systems Pty Ltd. The cables projected horizontally 550-mm away from the unexposed face of the wall and approximately 500 mm into the furnace chamber. The cables were supported at nominally 500-mm from the unexposed face of the plasterboard wall

Performance observed in respect of the following AS 1530.4-2014 criteria

Structural Adequacy - not applicable
Integrity - no failure at 91 minutes
Insulation - no failure at 91 minutes

and therefore for the purpose of Building Regulations in Australia, achieved a fire-resistance level (FRL) of -/60/60.

The fire resistance level (FRL) of the specimen is applicable when the system is exposed to fire from either direction. The maximum FRL of any test specimen cannot exceed the FRL achieved by the system in which it was installed. For the purposes of AS 1530.4-2014 the results of these fire tests may be used to directly assess fire hazard, but it should be noted that a single test method will not provide a full assessment of fire hazard under all fire conditions. This certificate is provided for general information only and does not comply with regulatory requirements for evidence of compliance.

Testing Officer: Peter Gordon Date of Test: 29 June 2020

Issued on the  $7^{\text{th}}$  day of September 2020 without alterations or additions.

Brett Roddy | Manager, Fire Testing and Assessments

"Copyright CSIRO 2020  $\mathbb{Q}$ "
Copying or alteration of this report without written authorisation from CSIRO is forbidden



This document is issued in accordance with NATA's accreditation requirements.

Accreditation No. 165 – Corporate Site No. 3625

Accredited for compliance with ISO/IEC 17025 - Testing

# **References**

The following informative documents are referred to in this Report:

AS 1530.4-2014	Methods for fire tests on building materials, components and structures Part 4: Fire-resistance tests for elements of building construction.
AS 4072.1-2005	Components for the protection of openings in fire-resistant separating elements. Part 1: Service penetrations and control joints.

\*\*\* end of report \*\*\*

#### **CONTACT US**

- t 1300 363 400 +61 3 9545 2176
- e enquiries@csiro.au
- w www.csiro.au

#### YOUR CSIRO

Australia is founding its future on science and innovation. Its national science agency, CSIRO, is a powerhouse of ideas, technologies and skills for building prosperity, growth, health and sustainability. It serves governments, industries, business and communities across the nation.

#### FOR FURTHER INFORMATION

#### **Infrastructure Technologies**

**Brett Roddy** 

Team Leader, Fire Testing and Assessments

- t +61 2 94905449
- e brett.roddy@csiro.au
- **w** https://www.csiro.au/en/Do-business/Services/Materials-infrastructure/Fire-safety