

Fire-resistance test on retrofit fire collars protecting a plasterboard wall penetrated by services

Test Report

Author: Peter Gordon Report number: FSP 2206

Date: 25 October 2021

Client: IG6 Pty Ltd as trustee for the IG6 IP Trust

Commercial-in-confidence



Inquiries should be addressed to:

Fire Testing and Assessments Author The Client

NATA Registered Laboratory Infrastructure Technologies IG6 Pty Ltd as trustee for the IG6 IP Trust 14 Julius Avenue 14 Julius Avenue 3 Skirmish Court

14 Julius Avenue14 Julius Avenue3 Skirmish CourtNorth Ryde, NSW 2113North Ryde, NSW 2113Victoria Point QLD 4165Telephone +61 2 9490 5444Telephone +61 2 9490 5500Telephone: +61 4 3390 5420

Report Status and Revision History:

VERSION	STATUS	DATE	DISTRIBUTION	ISSUE NUMBER
Revision A	Draft for review	27/06/2021	CSIRO / Client	FSP 2206
Revision B	Final for issue	25/10/2021	CSIRO / Client	FSP 2206

Report Authorisation:

AUTHOR	REVIEWED BY	AUTHORISED BY
Peter Gordon	Glenn Williams	Brett Roddy
Pebloman	g. Williams	B. Rong
25 October2021	25 October 2021	25 October 2021

Use of Reports - Testing

This report is subject to binding obligations under which it was prepared. In particular, the Report must not be used:

- as a means of endorsement; or
- in a company prospectus or notification to a Stock Exchange document for capital raising, without the prior written consent of CSIRO.

The Report may be published verbatim and in full, provided that a statement is included on the publication that it is a copy of the Report issued by CSIRO.

Excerpts of the Report may not be published.

Use of Reports – Consultancy

This report is subject to binding obligations under which it was prepared. In particular, the Report may only be used for the following purposes:

- the information in the Report may be used by the party that commissioned the Report for its internal business operations (but not licensing to third parties);
- the report may be copied for distribution within the organisation that commissioned the Report;
- copies of the Report (or extracts of the Report) may be distributed to contractors and agents of the organisation that commissioned the Report who have a need for the Report for its internal business operations. Any extracts of the Report distributed for this purpose must clearly note that the extract is part of a larger Report held by the organisation that commissioned the Report and which has been prepared by CSIRO.

The name, trade mark or logo of the CSIRO must not be used without the prior written consent of CSIRO.

The Report must not be used as a means of endorsement without the prior written consent of CSIRO.

Copyright and disclaimer

© 2021 CSIRO To the extent permitted by law, all rights are reserved and no part of this publication covered by copyright may be reproduced or copied in any form or by any means except with the written permission of CSIRO.

Important disclaimer

CSIRO advises that the information contained in this publication comprises general statements based on scientific research. The reader is advised and needs to be aware that such information may be incomplete or unable to be used in any specific situation. No reliance or actions must therefore be made on that information without seeking prior expert professional, scientific and technical advice. To the extent permitted by law, CSIRO (including its employees and consultants) excludes all liability to any person for any consequences, including but not limited to all losses, damages, costs, expenses and any other compensation, arising directly or indirectly from using this publication (in part or in whole) and any information or material contained in it.

Contents

1	Intro	Introduction			
	1.1	Identification of specimen	6		
	1.2	Sponsor	6		
	1.3	Manufacturer	6		
	1.4	Test standard	6		
	1.5	Reference standard	6		
	1.6	Test number	7		
	1.7	Test date	7		
2	Desc	cription of specimen	7		
	2.1	General	7		
	2.2	Dimensions	11		
	2.3	Orientation	11		
	2.4	Conditioning	11		
	2.5	Selection, construction and installation of the specimen and the supporting co 11	nstruction		
3	Docu	umentation	12		
4	Equi	pment	12		
	4.1	Furnace	12		
	4.2	Temperature	13		
	4.3	Measurement system	13		
5	Amb	oient temperature	13		
6	Departure from standard				
7	Termination of test				
8	Test	results	13		
	8.1	Critical observations	13		
	8.2	Furnace temperature	14		
	8.3	Furnace severity	14		
	8.4	Specimen temperature	15		
	8.5	Performance	15		
9	Fire-	resistance level (FRL)	17		
10	Field	d of direct application of test results	17		
11	Test	ed by	17		
Appe	ndices .		18		
	Appe	endix A – Measurement location	18		
	Appe	endix B – Photographs	20		
	Appe	endix C – Test data charts	26		
	Appe	endix D – Layout and installation drawings	36		
	Appe	endix E – Specimen Drawings	45		
	Appe	endix F – Certificate(s) of Test	48		

Fire-resistance test on retrofit fire collars protecting a plasterboard wall penetrated by services Sponsored Investigation No. FSP 2206

1 Introduction

1.1 Identification of specimen

The sponsor identified the specimen as retrofit fire collars protecting a steel framed plasterboard wall penetrated by two (2) polyvinyl chloride (PVC) pipes, a chlorinated polyvinyl chloride (CPVC) pipe, four (4) cross-linked high-density polyethylene (PE-Xa) pipes and a composite cross-linked high-density polyethylene (Pex-Al-Pex) pipe.

1.2 Sponsor

IG6 Pty Ltd as trustee for the IG6 IP Trust 3 Skirmish Court Victoria Point QLD 4165 Australia

1.3 Manufacturer

Snap Fire Systems Pty Ltd Building A, 1343 Wynnum Road Tingalpa QLD 4173 Australia

1.4 Test standard

Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4-2014, Fire-resistance tests for elements of construction.

Section 10: Service penetrations and control joints

1.5 Reference standard

Australian Standard 4072, Components for the protection of openings in fire-resistant separating elements, Part 1 - 2005, Service penetrations and control joints.

1.6 Test number

CSIRO Reference test number FS 5097/4603

1.7 Test date

The fire-resistance test was conducted on 8 June 2021.

2 Description of specimen

2.1 General

The plasterboard wall was constructed in accordance with Boral Firestop system SB120.1 with an established fire resistance level (FRL) of -/120/120 as detailed in the document titled "Plasterboard Fire and Acoustic Systems Australia", revision UB1231-SYS 12/18, by USG Boral Building Products Pty Ltd.

Construction comprised of 64-mm x 0.55-mm steel studs installed at nominally 600-mm centres, lined on each side with two layers of 13-mm thick Boral Firestop plasterboard sheets. The plasterboard sheeting was screw fixed to the steel studs using 6-gauge x 32-mm long plasterboard screws at nominally 200-mm centres. The plasterboard wall thickness was 116-mm from exposed face to unexposed face. The wall was penetrated by nine (9) pipes protected by retro-fitted Snap Fire Systems fire collars.

For the purpose of the test, the penetrations are referenced as Specimen 1, 2, 3, 4, 5, 6, 7, 8 and 9. Specimens 1, 2, 3, 4, 5, 6, 8 and 9 are the subject of this report. Documents containing a complete description of each specimen were supplied by the sponsor and are retained on file.

The pipes used in the test are stated to be manufactured in accordance with:

- Copper pipe AS 1432:2004 Copper tubes for plumbing, gas fitting and drainage applications;
- AS/NZS 1477:2017: PVC pipes and fittings for pressure applications;
- PE-Xa pipes AS/NZS 2492:2007: Cross-linked polyethylene (PE-X) pipes for pressure applications;
- Pex/Al/Pex pipe AS 4176.1-2010: Multilayer pipes for pressure applications Multilayer piping systems for hot and cold-water plumbing applications – General.

Specimen 1 - SNAP 50R Retrofit fire collars protecting a nominal 40 (48.25-mm OD) PN12 PVC pipe penetrating a 50-mm diameter aperture

The SNAP Retrofit 50R fire collar comprised a 0.75-mm steel casing with a 62-mm inner diameter and a 147-mm diameter base flange. The 47-mm high collar casing incorporated a closing mechanism which comprised two soft Intumesh intumescent wraps lined within the internal circumference of the collar. Intumescent A was 4-mm thick x 43-mm wide x 220-mm long, and Intumescent B was 4-mm thick x 43-mm wide x 200-mm long. Between the strips was a layer of 316 grade stainless steel mesh 210-mm long x 42-mm wide with a wire mesh diameter of 0.15-mm, as shown in drawing titled "SNAP 50 Retro", dated 18 January 2019, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the plasterboard wall in a back-to-back configuration using three 10 gauge 38-mm long coarse thread laminating screws.

The penetrating service comprised a Iplex PN12 PVC 48.25-mm outside diameter pipe, with a wall thickness of 3.46-mm fitted through the collar's sleeve and penetrated the wall through a 50-mm diameter cut-out hole as shown in drawing titled 'Specimen #1, 40 PN12 PVC Stack & 50R', dated 03 February 2021, provided by Snap Fire Systems Pty Ltd.

The pipe projected horizontally, 2000-mm away from the unexposed face of the wall and approximately 500-mm into the furnace chamber. The pipe was supported at nominally 500-mm and 1500-mm from the unexposed face of the plasterboard wall. The pipe was open at the unexposed end and plugged with ceramic fibre (Superwool) on the exposed end.

Specimen 2 - SNAP 32R Retrofit fire collars protecting a nominal 1-inch (33.5-mm OD) CPVC pipe penetrating a 35-mm diameter aperture

The SNAP 32R Retrofit collar comprised a 0.75-mm steel casing with a 40-mm inner diameter and a 106-mm diameter base flange. The 32-mm high collar casing incorporated a closing mechanism which comprised two soft Intumesh intumescent strips lined within the internal circumference of the collar. The inner and outer strips were 4-mm thick x 26-mm wide x 135-mm long, and 4-mm thick x 26-mm wide x 154-mm long, respectively. Between the strips was a layer of 316 stainless steel mesh 135 mm long x 25-mm wide with wire mesh diameter of 0.15-mm, as shown in drawing titled "SNAP 32 Retro", dated 5 October 2017, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the plasterboard wall in a back-to-back configuration using 10 gauge 38-mm long coarse thread laminating screws.

The penetrating service comprised a Blazemaster CPVC 33.5-mm outside diameter pipe, with a wall thickness of 2.9-mm fitted through the collar's sleeve and penetrated the wall through a 35-mm diameter cut-out hole as shown in drawing titled 'Specimen #2, 1 inch C-PVC Stack & 32R', dated 3 February 2021, provided by Snap Fire Systems Pty Ltd.

The pipe projected horizontally, 2000-mm away from the unexposed face of the wall and approximately 500-mm into the furnace chamber. The pipe was supported at nominally 500-mm and 1500-mm from the unexposed face of the plasterboard wall. The pipe was open at the unexposed end and plugged with ceramic fibre (Superwool) on the exposed end.

<u>Specimen 3 - SNAP 32R Retrofit fire collars protecting a nominal 32-mm PE-Xa Rehau Rautitan pipe penetrating a 40-mm diameter aperture</u>

The SNAP 32R Retrofit collar comprised a 0.75-mm steel casing with a 40 mm inner diameter and a 106-mm diameter base flange. The 32-mm high collar casing incorporated a closing mechanism which comprised two soft Intumesh intumescent strips lined within the internal circumference of the collar. The inner and outer strips were 4-mm thick x 26-mm wide x 135-mm long, and 4-mm thick x 26-mm wide x 154-mm long, respectively. Between the strips was a layer of 316 stainless steel mesh 135 mm long x 25-mm wide with a wire mesh diameter of 0.15-mm, as shown in drawing titled "SNAP 32 Retro", dated 5 October 2017, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the plasterboard wall in a back-to-back configuration using three 10 gauge 38-mm long coarse threaded laminating screws.

The penetrating service comprised a Rehau Rautitan PE-Xa 32.2-mm outside diameter pipe, with a wall thickness of 4.6-mm fitted through the collar's sleeve and penetrated the wall through a 40-mm diameter cut-out hole as shown in drawing titled 'Specimen #3, 32 Pex-a Stack & 32R', dated 03 February 2021, provided by Snap Fire Systems Pty Ltd.

The pipe projected horizontally, 2000-mm away from the unexposed face of the wall and approximately 500-mm into the furnace chamber. The pipe was supported at nominally 500-mm and 1500-mm from the unexposed face of the plasterboard wall. The pipe was open at the unexposed end and plugged with ceramic fibre (Superwool) on the exposed end.

<u>Specimen 4 - SNAP 32R Retrofit fire collars protecting a nominal 25-mm PE-Xa Rehau Rautitan pipe</u> penetrating a 32-mm diameter aperture

The SNAP 32R Retrofit collar comprised a 0.75-mm steel casing with a 40 mm inner diameter and a 106-mm diameter base flange. The 32-mm high collar casing incorporated a closing mechanism which comprised two soft Intumesh intumescent strips lined within the internal circumference of the collar. The inner and outer strips were 4-mm thick x 26-mm wide x 135-mm long and 4-mm thick x 26-mm wide x 154-mm long respectively. Between the strips was a layer of 316 stainless steel mesh 135 mm long x 25-mm wide with wire mesh diameter of 0.15-mm, as shown in drawing titled "SNAP 32 Retro", dated 5 October 2017, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the plasterboard wall in a back-to-back configuration using three 10 gauge 38-mm long coarse threaded laminating screws.

The penetrating service comprised a Rehau Rautitan PE-Xa 25.1-mm outside diameter pipe, with a wall thickness of 3.73-mm fitted through the collar's sleeve and penetrated the wall through a 32-mm diameter cut-out hole as shown in drawing titled 'Specimen #4, 25 Pex-a Stack & 32R', dated 3 February 2021, provided by Snap Fire Systems Pty Ltd.

The pipe projected horizontally, 2000-mm away from the unexposed face of the wall and approximately 500-mm into the furnace chamber. The pipe was supported at nominally 500-mm and 1500-mm from the unexposed face of the plasterboard wall. The pipe was open at the unexposed end and plugged with ceramic fibre (Superwool) on the exposed end.

<u>Specimen 5 - SNAP 32R Retrofit fire collars protecting a nominal 20-mm PE-Xa Rehau Rautitan pipe penetrating a 29-mm diameter aperture</u>

The SNAP 32R Retrofit collar comprised a 0.75-mm steel casing with a 40 mm inner diameter and a 106-mm diameter base flange. The 32-mm high collar casing incorporated a closing mechanism which comprised two soft Intumesh intumescent strips lined within the internal circumference of the collar. The inner and outer strips were 4-mm thick x 26-mm wide x 135-mm long, and 4-mm thick x 26-mm wide x 154-mm long, respectively. Between the strips was a layer of 316 stainless steel mesh 135 mm long x 25-mm wide with wire mesh diameter of 0.15-mm, as shown in drawing titled "SNAP 32 Retro", dated 5 October 2017, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the plasterboard wall in a back-to-back configuration using three 10 gauge 38-mm long coarse threaded laminating screws.

The penetrating service comprised a Rehau Rautitan PE-Xa 20.2-mm outside diameter pipe, with a wall thickness of 3.5-mm fitted through the collar's sleeve and penetrated the wall through a 29-mm diameter cut-out hole as shown in drawing titled 'Specimen #5, 20 Pex-a Stack & 32R', dated 3 February 2021, provided by Snap Fire Systems Pty Ltd.

The pipe projected horizontally, 2000-mm away from the unexposed face of the wall and approximately 500-mm into the furnace chamber. The pipe was supported at nominally 500-mm and 1500-mm from the unexposed face of the plasterboard wall. The pipe was open at the unexposed end and plugged with ceramic fibre (Superwool) on the exposed end.

<u>Specimen 6 - SNAP 32R Retrofit fire collars protecting a nominal 16-mm PE-Xa Rehau Rautitan pipe penetrating a 25-mm diameter aperture</u>

The SNAP 32R Retrofit collar comprised a 0.75-mm steel casing with a 40 mm inner diameter and a 106-mm diameter base flange. The 32-mm high collar casing incorporated a closing mechanism which comprised two soft Intumesh intumescent strips lined within the internal circumference of the collar. The inner and outer strips were 4-mm thick x 26-mm wide x 135-mm long, and 4-mm thick x 26-mm wide x 154-mm long, respectively. Between the strips was a layer of 316 stainless steel mesh 135 mm long x 25-mm wide with wire mesh diameter of 0.15-mm, as shown in drawing titled "SNAP 32 Retro", dated 5 October 2017, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the plasterboard wall in a back-to-back configuration using three 10 gauge 38-mm long coarse threaded laminating screws.

The penetrating service comprised a Rehau Rautitan PE-Xa 16.1-mm outside diameter pipe, with a wall thickness of 2.6-mm fitted through the collar's sleeve and penetrated the wall through a 25-mm diameter cut-out hole as shown in drawing titled 'Specimen #6, 16 Pex-a Stack & 32R', dated 3 February 2021, provided by Snap Fire Systems Pty Ltd.

The pipe projected horizontally, 2000-mm away from the unexposed face of the wall and approximately 500-mm into the furnace chamber. The pipe was supported at nominally 500-mm and 1500-mm from the unexposed face of the plasterboard wall. The pipe was open at the unexposed end and plugged with ceramic fibre (Superwool) on the exposed end.

<u>Specimen 8 - SNAP 32R Retrofit fire collars protecting a nominal 25-mm Pex-Al-Pex pipe penetrating a 32-mm diameter aperture</u>

The SNAP 32R Retrofit collar comprised a 0.75-mm steel casing with a 40-mm inner diameter and a 106-mm diameter base flange. The 32-mm high collar casing incorporated a closing mechanism which comprised two soft Intumesh intumescent strips lined within the internal circumference of the collar. The inner and outer strips were 4-mm thick x 26-mm wide x 135-mm long, and 4-mm thick x 26-mm wide x 154-mm long, respectively. Between the strips was a layer of 316 stainless steel mesh 135 mm long x 25-mm wide with wire mesh diameter of 0.15-mm, as shown in drawing titled "SNAP 32 Retro", dated 5 October 2017, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the plasterboard wall in a back-to-back configuration using three 10 gauge 38-mm long coarse thread laminating screws.

The penetrating service comprised a CXL Pex-Al-Pex 25.15-mm outside diameter pipe, with a wall thickness of 2.75-mm fitted through the collar's sleeve and penetrated the wall through a 32-mm diameter cut-out hole as shown in drawing titled 'Specimen #8 25 Pex-Al-Pex Stack & 32R', dated 3 February 2021, provided by Snap Fire Systems Pty Ltd.

The pipe projected horizontally, 2000-mm away from the unexposed face of the wall and approximately 500 mm into the furnace chamber. The pipe was supported at nominally 500-mm and 1500-mm from the unexposed face of the plasterboard wall. The pipe was open at the unexposed end and plugged with ceramic fibre (Superwool) on the exposed end.

Specimen 9 - SNAP MS70R Multi Services Retrofit fire collars protecting a nominal 32 (42.2-mm OD) PN12 PVC pipe with 19-mm thick fire rated lagging penetrating a 70-mm diameter aperture

The SNAP MS70R Multi Service Retrofit fire collar comprised a 0.75-mm thick steel casing with a 69-mm inner diameter and a 0.95-mm thick steel base flange with a 162-mm diameter. The 95-mm high collar casing incorporated a 4-mm thick x 90-mm wide x 250-mm long soft Intumesh intumescent wrap lined within the internal circumference of the collar casing. The closing mechanism comprised three stainless steel springs, a nylon fuse link and a 258-mm long x 88-mm wide 316 stainless steel mesh located around the intumescent strip, as shown in drawing titled 'SNAP 70 Multi Service Retro', dated 23 September 2019, by Snap Fire Systems Pty Ltd. One collar was fixed to each side of the plasterboard wall in a back-to-back configuration using three M4 expandable steel hollow wall anchors with stainless steel washers.

The penetrating service comprised a Iplex PN12 PVC 42.2-mm outside diameter pipe, with a wall thickness of 2.57-mm covered with 19-mm thick Armaflex FR foam lagging. The lagged pipe was fitted through the collar's sleeve and penetrated the wall through a 70-mm diameter cut-out hole as shown in drawing titled 'Specimen #9 32 PN12 PVC Pipe with 19mm F/R Lagging & MS70R Collar', dated 3 February 2021, by Snap Fire Systems Pty Ltd.

The lagged pipe projected horizontally 2000-mm away from the unexposed face of the wall and approximately 500-mm into the furnace chamber. The lagged pipe was supported at 500-mm and 1500-mm from the unexposed face of the plasterboard wall. The pipe was open at the unexposed end and plugged with ceramic fibre (Superwool) on the exposed end.

2.2 Dimensions

The plasterboard wall was nominally 1150-mm wide x 1150-mm high x 116-mm thick.

2.3 Orientation

The plasterboard wall was placed vertically against the furnace chamber and subjected to fire exposure from one side only.

2.4 Conditioning

The specimen was delivered on 18 May 2021 and stored under standard laboratory atmospheric conditions until the test date.

2.5 Selection, construction and installation of the specimen and the supporting construction

The supporting wall construction and specimen installation was organised by the sponsor. CSIRO was not involved in the selection of the materials.

3 Documentation

The following documents were supplied or referenced by the sponsor as a complete description of the specimen and should be read in conjunction with this report:

Documents titled 'Plasterboard Fire and Acoustic Systems Australia', revision UB1231-SYS 12/18, by USG Boral Building Products Pty Ltd.

Drawing titled 'Test Wall W-21-B Layout', dated 3 February 2021, by Snap Fire Systems Pty Ltd.

Drawing titled 'Specimen #1, 40 PN12 PVC Stack & 50R', dated 03 February 2021, provided by Snap Fire Systems Pty Ltd.

Drawing titled 'Specimen #2, 1-inch C-PVC Stack & 32R', dated 3 February 2021, provided by Snap Fire Systems Pty Ltd.

Drawing titled 'Specimen #3, 32 Pex-a Stack & 32R', dated 03 February 2021, provided by Snap Fire Systems Pty Ltd.

Drawing titled 'Specimen #4, 25 Pex-a Stack & 32R', dated 3 February 2021, provided by Snap Fire Systems Pty Ltd.

Drawing titled 'Specimen #5, 20 Pex-a Stack & 32R', dated 3 February 2021, provided by Snap Fire Systems Pty Ltd.

Drawing titled 'Specimen #6, 16 Pex-a Stack & 32R', dated 3 February 2021, provided by Snap Fire Systems Pty Ltd.

Drawing titled 'Specimen #8, 25 Pex-Al-Pex Stack & 32R', dated 3 February 2021, provided by Snap Fire Systems Pty Ltd.

Drawing titled 'Specimen #9, 32 PN12 PVC Pipe with 19mm F/R Lagging & MS70R Collar', dated 3 February 2021, provided by Snap Fire Systems Pty Ltd.

Drawing title 'SNAP 32 Retro', dated 5 October 2017, by Snap Fire Systems Pty Ltd.

Drawing title 'SNAP 50 Retro', dated 18 January 2019, by Snap Fire Systems Pty Ltd.

Drawing titled 'SNAP 70 Multi Service Retro', dated 23 September 2019, by Snap Fire Systems Pty Ltd.

4 Equipment

4.1 Furnace

The furnace had a nominal opening of 1000-mm x 1000-mm for attachment of vertical or horizontal specimens.

The furnace was lined with refractory bricks and materials with the thermal properties as specified in AS 1530.4-2014 and was heated by combustion of a mixture of natural gas and air.

4.2 Temperature

The temperature in the furnace chamber was measured by four type K, 3-mm diameter, and 310 stainless steel Mineral Insulated Metal Sheathed (MIMS) thermocouples. Each thermocouple was housed in high-nickel steel tubes opened at the exposed end.

The temperatures of the specimen were measured by glass-fibre insulated and sheathed K-type thermocouples with a wire diameter of 0.5-mm.

Location of the thermocouples on the unexposed face of the specimen are described in Appendix A.

4.3 Measurement system

The primary measurement system comprised a multiple-channel data logger, scanning at one-minute intervals during the test.

5 Ambient temperature

The temperature of the test area was 16°C at the commencement of the test.

6 Departure from standard

There were no departures from the requirements of AS 1530.4-2014.

7 Termination of test

The test was terminated at 181 minutes by the agreement with the sponsor.

8 Test results

8.1 Critical observations

The following observations were made during the fire-resistance test:

T!	Observation
Time	Observation
1 minutes -	Smoke is being emitted between the collar and the pipe of at the base of
	Specimens 4, 5, 6 and 8.
2 minutes -	Smoke is being emitted between the collar and the pipe of Specimen 2. Smoke
	has begun fluing from the end of the pipes of Specimens 1, 2 and 6.
3 minutes -	Smoke has begun fluing from the end of the pipes of Specimens 3 and 4.
4 minutes -	Smoke has begun fluing from the end of the pipes of Specimens 8 and 9.
4½ minutes -	Smoke has begun fluing from the end of the pipe of all specimen 5.

6 minutes - Smoke has ceased fluing from the collars at the base of Specimens 2, 4, 5, 6, 8 and 9. 8 minutes -Light smoke has resumed fluing from the end of the pipe of specimens 4 and 9. 44 minutes - Smoke is being emitted from the collar at the base of Specimens 8. The lagging has begun to swell at the base of Specimen 8. 48 minutes -56 minutes -Smoke is being emitted from the collar at the base of Specimen 6. 85 minutes - Smoke has resumed fluing from the end of the pipe of Specimen 4. 90 minutes - Smoke has resumed fluing from the end of the pipe of Specimens 3, 4, 5, and 6. 128 minutes -Smoke continues fluing from the end of the pipes of Specimens 1, 2, 3 and 5. 142 minutes -<u>Insulation failure of Specimen 5</u> – maximum temperature rise of 180K is exceeded on the top of the pipe, 25-mm from the collar. The collars of Specimens 4, 5 and 6 have begun to discolour. 150 minutes -The intumescent material inside the fire collar on the unexposed face of Specimen 5 has begun to swell. 159 minutes -<u>Insulation failure of Specimen 8</u> – maximum temperature rise of 180K is exceeded on the top of the collar. 160 minutes -The plasterboard wall around the collars of Specimens 5 and 8 have begun to discolour. 163 minutes -Insulation Failure of Specimen 4 – maximum temperature rise of 180K is exceeded on the top of the pipe, 25-mm from the collar. 165 minutes -The intumescent from the exposed collar of Specimen 8 has begun to activate. The intumescent material inside the fire collar on the unexposed face of 169 minutes -Specimen 6 has begun to swell. The plasterboard wall around the collars of Specimens 1, 2, and 3 has begun to 173 minutes discolour. 175 minutes -Insulation Failure of Specimen 6 – maximum temperature rise of 180K is

8.2 Furnace temperature

Test terminated.

181 minutes -

Figure 1 shows the standard curves of temperature versus time for heating the furnace chamber and the actual curves of average and maximum temperature versus time recorded during the heating period.

exceeded on the top of the pipe, 25-mm from the collar.

exceeded on the plasterboard wall 25-mm above the collar.

Insulation Failure of Specimen 9 – maximum temperature rise of 180K is

8.3 Furnace severity

Figure 2 shows the curve of furnace severity versus time during the heating period.

8.4 Specimen temperature

Figure 3 shows the curve of temperature versus time associated with Specimen 1.

Figure 4 shows the curve of temperature versus time associated with Specimen 2.

Figure 5 shows the curve of temperature versus time associated with Specimen 3.

Figure 6 shows the curve of temperature versus time associated with Specimen 4.

Figure 7 shows the curve of temperature versus time associated with Specimen 5.

Figure 8 shows the curve of temperature versus time associated with Specimen 6.

Figure 9 shows the curve of temperature versus time associated with Specimen 8.

Figure 10 shows the curve of temperature versus time associated with Specimen 9.

8.5 Performance

Performance observed in respect of the following AS 1530.4-2014 criteria:

<u>Specimen 1 - SNAP 50R Retrofit fire collars protecting a nominal 40 (48.25-mm OD)</u> <u>PN12 PVC pipe penetrating a 50-mm diameter aperture</u>

Structural adequacy - not applicable
Integrity - no failure at 181 minutes
Insulation - no failure at 181 minutes

<u>Specimen 2 - SNAP 32R Retrofit fire collars protecting a nominal 1-inch (33.5-mm OD)</u> <u>CPVC pipe penetrating a 35-mm diameter aperture</u>

Structural adequacy - not applicable
Integrity - no failure at 181 minutes
Insulation - no failure at 181 minutes

<u>Specimen 3 - SNAP 32R Retrofit fire collars protecting a nominal 32-mm PE-Xa Rehau Rautitan pipe penetrating a 40-mm diameter aperture</u>

Structural adequacy - not applicable
Integrity - no failure at 181 minutes
Insulation - no failure at 181 minutes

<u>Specimen 4 - SNAP 32R Retrofit fire collars protecting a nominal 25-mm PE-Xa Rehau</u> Rautitan pipe penetrating a 32-mm diameter aperture

Structural adequacy - not applicable
Integrity - no failure at 181 minutes
Insulation - 163 minutes

<u>Specimen 5 - SNAP 32R Retrofit fire collars protecting a nominal 20-mm PE-Xa Rehau</u> <u>Rautitan pipe penetrating a 29-mm diameter aperture</u>

Structural adequacy -

Integrity

not applicable no failure at 181 minutes

Insulation -

142 minutes

<u>Specimen 6 - SNAP 32R Retrofit fire collars protecting a nominal 16-mm PE-Xa Rehau</u> Rautitan pipe penetrating a 25-mm diameter aperture

Structural adequacy - not applicable Integrity - no failure at 181 minutes Insulation - 175 minutes

<u>Specimen 8 - SNAP 32R Retrofit fire collars protecting a nominal 25-mm PE-Xa/Al/PE pipe</u> penetrating a 32-mm diameter aperture

Structural adequacy - not applicable
Integrity - no failure at 181 minutes
Insulation - 159 minutes

Specimen 9 - SNAP MS70R Multi Services Retrofit fire collars protecting a nominal 32 (42.2-mm OD) PN12 PVC pipe with 19-mm thick fire rated lagging penetrating a 70-mm diameter aperture.

Structural adequacy - not applicable
Integrity - no failure at 181 minutes
Insulation - 181 minutes

This report details methods of construction, the test conditions and the results obtained when the specific element of construction described herein was tested following the procedure outlined in AS 1530.4. Any significant variation with respect to size, constructional details, loads, stresses, edge or end conditions, other than those allowed under the field of direct application in the relevant test method, is not covered by this report.

Because of the nature of fire resistance testing and the consequent difficulty in quantifying the uncertainty of measurement of fire resistance, it is not possible to provide a stated degree of accuracy of the result.

9 Fire-resistance level (FRL)

For the purpose of building regulations in Australia, the FRL's of the test specimens were as follows:

Specimen 1 -/120/120 Specimen 2 -/120/120 -/120/120 Specimen 3 Specimen 4 -/120/120 Specimen 5 -/120/120 Specimen 6 -/120/120 Specimen 8 -/120/120 Specimen 9 -/120/120

The fire-resistance level is applicable when the system is exposed to fire from either direction.

The test was conducted on a wall system with an established FRL of -/120/120. The maximum FRL of any test specimen cannot exceed the FRL achieved by the wall system in which it was installed.

For the purposes of AS 1530.4-2014 the results of these fire tests may be used to directly assess fire hazard, but it should be noted that a single test method will not provide a full assessment of fire hazard under all fire conditions.

10 Field of direct application of test results

The results of the fire test contained in this test report are directly applicable, without reference to the testing authority, to similar constructions where one or more changes listed in Clause 10.12 of AS 1530.4-2014, have been made provided no individual component is removed or reduced.

11 Tested by

Peter Gordon Testing Officer

Appendices

Appendix A – Measurement location

SPECIMEN	THERMCOUPLE POSITION	DESIGNATION
	On P/B wall, 25-mm above of collar	S1
Specimen 1 - SNAP 50R Retrofit	On P/B wall, 25-mm below of collar (S/E)	S2
fire collars protecting a nominal 40 (48.25-mm OD) PN12 PVC	On collar top right side	S3
pipe penetrating a 50-mm	On collar bottom right side	S4
diameter aperture.	On top left of pipe, 25-mm from collar	S5
	On bottom right of pipe, 25-mm from collar	S6
	On P/B wall, 25-mm from collar left side	S7
Specimen 2 - SNAP 32R Retrofit	On P/B wall, 25-mm from collar right side	S8
fire collars protecting a nominal 1-inch (33.5-mm OD) CPVC pipe	On collar left side	S9
penetrating a 35-mm diameter	On collar right side	S10
aperture.	On top of pipe, 25-mm from collar	S11
	On bottom of pipe, 25-mm from collar	S12
	On P/B wall, 25-mm left of collar	S13
Specimen 3 - SNAP 32R Retrofit	On P/B wall, 25-mm right of collar	S14
fire collars protecting a nominal 32-mm PE-Xa Rehau Rautitan	On collar left side	S15
pipe penetrating a 40-mm	On collar right side	S16
diameter aperture.	On top of pipe, 25-mm from collar	S17
	On right side of pipe, 25-mm from collar	S18
	On P/B wall, 25-mm above collar	S19
Specimen 4 - SNAP 32R Retrofit	On P/B wall, 25-mm below of collar	S20
fire collars protecting a nominal	On collar top side	S21
25-mm PE-Xa Rehau Rautitan pipe penetrating a 32-mm	On collar bottom side	S22
diameter aperture.	On top of pipe, 25-mm from collar	S23
	On bottom of pipe, 25-mm from collar	S24
	On P/B wall, 25-mm left collar	S25
Specimen 5 - SNAP 32R Retrofit	On P/B wall, 25-mm right of collar	S26
fire collars protecting a nominal 20-mm PE-Xa Rehau Rautitan	On collar top side	S27
pipe penetrating a 29-mm	On collar bottom side	S28
diameter aperture.	On top of pipe, 25-mm from collar	S29
	On bottom of pipe, 25-mm from collar	S30

SPECIMEN	THERMCOUPLE POSITION	DESIGNATION	
	On P/B wall, 25-mm left collar	S31	
Specimen 6 - SNAP 32R Retrofit	On P/B wall, 25-mm right of collar	S32	
fire collars protecting a nominal 16-mm PE-Xa Rehau Rautitan	On collar top side	S33	
pipe penetrating a 25-mm	On collar bottom side	S34	
diameter aperture.	On top of pipe, 25-mm from collar	S35	
	On bottom of pipe, 25-mm from collar	S36	
	On P/B wall, 25-mm above collar	S43	
Specimen 8 - SNAP 32R Retrofit	On P/B wall, 25-mm below of collar	S44	
fire collars protecting a nominal	On collar top right side	S45	
25-mm Pex/Al/Pex pipe penetrating a 32-mm diameter	On collar bottom right side	S46	
aperture.	On top of pipe, 25-mm from collar	S47	
	On bottom of pipe, 25-mm from collar	S48	
	On P/B wall, 25-mm above collar	S49	
Specimen 9 SNAP MS70R Multi	On P/B wall, 25-mm below of collar	S50	
Services Retrofit fire collars protecting a nominal 32	On collar top right side	S51	
(42.2-mm OD) PN12 PVC pipe	On collar left side	S52	
with 19-mm thick fire rated lagging penetrating a 70-mm	On top of lagged pipe, 25-mm from collar	S53	
diameter aperture.	On bottom of lagged pipe, 25-mm from collar	S54	
Roving thermocouple		S55	
Ambient thermocouple		S56	


Appendix B – Photographs



PHOTOGRAPH 1 – UNEXPOSED FACE OF SPECIMENS PRIOR TO TESTING



PHOTOGRAPH 2 – EXPOSED FACE OF SPECIMENS PRIOR TO TESTING



PHOTOGRAPH 3 – SPECIMENS AFTER 4 MINUTES OF TESTING



PHOTOGRAPH 4 – SPECIMENS AFTER 5 MINUTES OF TESTING



PHOTOGRAPH 5 – SPECIMENS AFTER 30 MINUTES OF TESTING



PHOTOGRAPH 6 – SPECIMENS AFTER 60 MINUTES OF TESTING



PHOTOGRAPH 7 – SPECIMENS AFTER 90 MINUTES OF TESTING



PHOTOGRAPH 8 – SPECIMENS AFTER 120 MINUTES OF TESTING



PHOTOGRAPH 9 - SPECIMENS AFTER 150 MINUTES OF TESTING



PHOTOGRAPH 10 – SPECIMENS AFTER 180 MINUTES OF TESTING



PHOTOGRAPH 11 – EXPOSED FACE OF SPECIMENS AT CONCLUSION OF TESTING

Appendix C – Test data charts




FIGURE 1 – FURNACE TEMPERATURE




FIGURE 2 – FURNACE SEVERITY




FIGURE 3 - TEMPERATURE VERSUS TIME ASSOCIATED WITH SPECIMEN #1




FIGURE 4 - TEMPERATURE VERSUS TIME ASSOCIATED WITH SPECIMEN #2




FIGURE 5 - TEMPERATURE VERSUS TIME ASSOCIATED WITH SPECIMEN #3




FIGURE 6 - TEMPERATURE VERSUS TIME ASSOCIATED WITH SPECIMEN #4




FIGURE 7 - TEMPERATURE VERSUS TIME ASSOCIATED WITH SPECIMEN #5




FIGURE 8 - TEMPERATURE VERSUS TIME ASSOCIATED WITH SPECIMEN #6




FIGURE 9 - TEMPERATURE VERSUS TIME ASSOCIATED WITH SPECIMEN #8





FIGURE 10 - TEMPERATURE VERSUS TIME ASSOCIATED WITH SPECIMEN #9

Appendix D – Layout and installation drawings

Snap Fire Systems Pty Ltd Test Wall W-21-B Layout

Date: 03 FEB 2021




Penetration	Collar Code	Pipe Type	Pipe Diameter
1	50R	PVC PN12	40
2	32R	C-PVC	1 in
3	32R	PEX-a	32
4	32R	PEX-a	25
5	32R	PEX-a	20
6	32R	PEX-a	16
8	32R	PEX-AI-PEX	25
9	MS70R	PVC PN12 + Armaflex Lagging	32 (19mm Lagging)

DRAWING TITLED 'TEST WALL W-21-B LAYOUT, DATED 3 FEBRUARY 2021, BY SNAP FIRE SYSTEMS PTY LTD.


Specimen #1 40 PN12 PVC Stack & 50R

Date: 03 FEB 2021




DRAWING TITLED 'SPECIMEN #1 40 PN12 PVC STACK & 50R', DATED 3 FEBRUARY 2021, BY SNAP FIRE SYSTEMS PTY LTD

Specimen #2 1inch C-PVC Stack & 32R Date: 03 FEB 2021




Specimen #3 32 Pex-a Stack & 32R Date: 03 FEB 2021



DRAWING TITLED 'SPECIMEN #3 32 PEX-A STACK & 32R', DATED 3 FEBRUARY 2021, BY SNAP FIRE SNAP FIRE SYSTEMS PTY LTD


Specimen #4 25 Pex-a Stack & 32R

Date: 03 FEB 2021



DRAWING TITLED 'SPECIMEN #4 25 PEX-A STACK & 32R', DATED 3 FEBRUARY 2021, BY SNAP FIRE SYSTEMS PTY LTD


Specimen #5 20 Pex-a Stack & 32R Date: 03 FEB 2021



DRAWING TITLED 'SPECIMEN #5 20 PEX-A STACK & 32R', DATED 3 FEBRUARY 2021, BY SNAP FIRE SYSTEMS PTY LTD


Specimen #6 16 Pex-a Stack & 32R

Date: 03 FEB 2021



DRAWING TITLED 'SPECIMEN #6 16 PEX-A STACK & 32R', DATED 3 FEBRUARY 2021, BY SNAP FIRE SNAP FIRE SYSTEMS PTY LTD


Specimen #8 25 Pex-Al-Pex Stack & 32R Date: 03 FEB 2021



DRAWING TITLED 'SPECIMEN #8 25 PEX-A-PEX STACK & 32R', DATED 3 FEBRUARY 2021, BY SNAP FIRE SYSTEMS PTY LTD


Specimen #9

32 PN12 PVC Pipe with 19mm F/R Lagging & MS70R Collar Date: 03 FEB 2021




DRAWING TITLED 'SPECIMEN #9 32 PN12 PVC PIPEWITH 19MM F/R LAGGING STACK & MS70R COLLAR',
DATED 3 FEBRUARY 2021, BY SNAP FIRE SNAP FIRE SYSTEMS PTY LTD


Appendix E – Specimen Drawings



DRAWING TITLED 'SNAP 32 RETRO', DATED 5 OCTOBER 2017, BY SNAP FIRE SYSTEMS.



DRAWING TITLED 'SNAP 70 MULTI SERVICE RETRO', DATED 23 SEPTEMBER 2019, BY SNAP FIRE SYSTEMS.



DRAWING TITLED 'SNAP 50 RETRO', DATED 18 JANUARY 2019, BY SNAP FIRE SYSTEMS.

Appendix F – Certificate(s) of Test

INFRASTRUCTURE TECHNOLOGIES

www.csiro.au

14 Julius Avenue, North Ryde NSW 2113 PO Box 52, North Ryde NSW 1670, Australia T (02) 9490 5444 • ABN 41 687 119 230



Certificate of Test

No. 3613

This is to certify that the element of construction described below was tested by CSIRO Infrastructure Technologies in accordance with Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4 Fire-resistance tests of elements of construction, 2014, Section 10: Service penetrations and control joints, on behalf of:

IG6 Pty Ltd as trustee for the IG6 IP Trust

3 Skirmish Court

Victoria Point Old 4165

A full description of the test specimen and the complete test results are detailed in the Division's report numbered FSP 2206.

Product Name: SNAP 50R Retrofit fire collars protecting a nominal 40 (48.25-mm OD) PN12 PVC pipe penetrating a 50-mm diameter

aperture (Specimen 1)

Description:

The sponsor identified the specimen as retrofit fire collars protecting a steel framed plasterboard wall penetrated nine (9) pipes. The plasterboard wall was constructed in accordance with Boral Firestop system SB120.1 with an established fire resistance level (FRL) of -/120/120. Specimen 1 is the subject of this Certificate. The SNAP Retrofit 50R fire collar comprised a 0.75-mm steel casing with a 62 mm inner diameter and a 147-mm diameter base flange. The 47-mm high collar casing incorporated a closing mechanism which comprised two soft intumesh intumescent wraps lined within the internal circumference of the collar. Intumescent A was 4-mm thick x 43-mm wide x 220-mm long, and intumescent B was 4 mm thick x 43-mm wide x 200-mm long. Between the strips was a layer of 316 grade stainless steel mesh 210-mm long x 42-mm wide with a wire mesh diameter of 0.15 mm. One collar was fixed to each side of the plasterboard wall in a back-to-back configuration using three 10 gauge 38-mm long coarse thread laminating screws. The penetrating service comprised a Iplex PN12 PVC 48.25-mm outside diameter pipe, with a wall thickness of 3.46-mm fitted through the collar's sleeve and penetrated the wall through a 50 mm diameter cut-out hole. The pipe projected horizontally, 2000-mm away from the unexposed face of the wall and approximately 500 mm into the furnace chamber. The pipe was supported at nominally 500-mm and 1500-mm from the unexposed face of the plasterboard wall. The pipe was open at the unexposed end and plugged with ceramic fibre (Superwool) on the exposed end. The Sponsor provided document titled 'Plasterboard Fire and Acoustic Systems Australia', revision UB1231-SYS 12/18, by USG Boral Building Products Pty Ltd, drawing titled 'Specimen #1, 40 PN12 PVC Stack & 50R', dated 03 February 2021, by Snap Fire Systems Pty Ltd and drawing titled "SNAP 50 Retro", dated 18 January 2019, by Snap Fire Systems Pty Ltd as a complete description of the specimen and should be read in conjunction with this Certificate.

Performance observed in respect of the following AS 1530.4-2014 criteria

Structural Adequacy

Integrity Insulation no failure at 181 minutes no failure at 181 minutes

and therefore for the purpose of Building Regulations in Australia, achieved a fire-resistance level (FRL) of -/120/120.

The fire-resistance level is applicable when the system is exposed to fire from either direction. The test was conducted on a wall system with an established FRL of -/120/120. The maximum FRL of any test specimen cannot exceed the FRL achieved by the wall system in which it was installed. For the purposes of AS 1530.4-2014 the results of these fire tests may be used to directly assess fire hazard, but it should be noted that a single test method will not provide a full assessment of fire hazard under all fire conditions. This certificate is provided for general information only and does not comply with regulatory requirements for evidence of compliance.

Peter Gordon

Issued on the 25th day of October 2021 without alterations or additions.

Brett Roddy | Manager, Fire Testing and Assessments

"Copyright CSIRO 2021 @" Copying or alteration of this report without written authorisation from CSIRO is forbidden



This document is issued in accordance with NATA's accreditation requirements Accreditation No. 165 - Corporate Site No. 3625 Accredited for compliance with ISO/IEC 17025 - Testing

www.cstro.au

14 Julius Avenue, North Ryde NSW 2113 PO Box 52, North Ryde NSW 1670, Australia T (02) 9490 5444 • ABN 41 687 119 230



Certificate of Test

No. 3614

This is to certify that the element of construction described below was tested by CSIRO Infrastructure Technologies in accordance with Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4 Fire-resistance tests of elements of construction, 2014, Section 10: Service penetrations and control joints, on behalf of:

IG6 Pty Ltd as trustee for the IG6 IP Trust

3 Skirmish Court Victoria Point Old 4165

A full description of the test specimen and the complete test results are detailed in the Division's report numbered FSP 2206.

Product Name: SNAP 32R Retrofit fire collars protecting a nominal 1-inch (33.5-mm OD) CPVC pipe penetrating a 35-mm diameter

aperture (Specimen 2)

Description:

The sponsor identified the specimen as retrofit fire collars protecting a steel framed plasterboard wall penetrated nine (9) pipes. The plasterboard wall was constructed in accordance with Boral Firestop system SB120.1 with an established fire resistance level (FRL) of -/120/120. Specimen 2 is the subject of this Certificate. The SNAP 32R Retrofit collar comprised a 0.75-mm steel casing with a 40-mm inner diameter and a 106-mm diameter base flange. The 32-mm high collar casing incorporated a closing mechanism which comprised two soft Intumesh intumescent strips lined within the Internal circumference of the collar. The inner and outer strips were 4-mm thick x 26-mm wide x 135-mm long, and 4-mm thick x 26-mm wide x 154-mm long, respectively. Between the strips was a layer of 316 stainless steel mesh 135 mm long x 25-mm wide with wire mesh diameter of 0.15-mm. One collar was fixed to each side of the plasterboard wall in a back-to-back configuration using 10 gauge 38-mm long coarse thread laminating screws. The penetrating service comprised a Blazemaster CPVC 33.5-mm outside diameter pipe, with a wall thickness of 2.9-mm fitted through the collar's sleeve and penetrated the wall through a 35 mm diameter cut-out hole. The pipe projected horizontally, 2000-mm away from the unexposed face of the wall and approximately 500 mm into the furnace chamber. The pipe was supported at nominally 500-mm and 1500-mm from the unexposed face of the plasterboard wall. The pipe was open at the unexposed end and plugged with ceramic fibre (Superwool) on the exposed end. The Sponsor provided document titled 'Plasterboard Fire and Acoustic Systems Australia', revision UB1231-SYS 12/18, by USG Boral Building Products Pty Ltd, drawing titled 'Specimen #2, 1 inch C-PVC Stack & 32R', dated 3 February 2021, by Snap Fire Systems Pty Ltd and drawing titled "SNAP 32 Retro", dated 5 October 2017, by Snap Fire Systems Pty Ltd as a complete description of the specimen and should be read in conjunction with this Certificate.

Performance observed in respect of the following AS 1530.4-2014 criteria

Structural Adequacy - not applicable Integrity - no failure at 181 minutes Insulation - no failure at 181 minutes

and therefore for the purpose of Building Regulations in Australia, achieved a fire-resistance level (FRL) of -/120/120.

The fire-resistance level is applicable when the system is exposed to fire from either direction. The test was conducted on a wall system with an established FRL of -/120/120. The maximum FRL of any test specimen cannot exceed the FRL achieved by the wall system in which it was installed. For the purposes of AS 1530.4-2014 the results of these fire tests may be used to directly assess fire hazard, but it should be noted that a single test method will not provide a full assessment of fire hazard under all fire conditions. This certificate is provided for general information only and does not comply with regulatory requirements for evidence of compliance.

Testing Officer: Peter Gordon

Issued on the 25th day of October 2021 without alterations or additions.

2 million bitch and a basinans

Date of Test:

8 June 2021

Brett Roddy | Manager, Fire Testing and Assessments

"Copyright CSIRO 2021 ©"
Copyring or alteration of this report without written authorisation from CSIRO is forbidden



This document is issued in accordance with NATA's accreditation requirements.

Accreditation No. 165 – Corporate Site No. 3625

Accredited for compliance with ISO/IEC 17025 - Testing

www.cstro.au

14 Julius Avenue, North Ryde NSW 2113 PO Box 52, North Ryde NSW 1670, Australia T (02) 9490 5444 • ABN 41 687 119 230



Certificate of Test

No. 3615

This is to certify that the element of construction described below was tested by CSIRO Infrastructure Technologies in accordance with Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4 Fire-resistance tests of elements of construction, 2014, Section 10: Service penetrations and control joints, on behalf of:

IG6 Pty Ltd as trustee for the IG6 IP Trust

3 Skirmish Court Victoria Point Old 4165

A full description of the test specimen and the complete test results are detailed in the Division's report numbered FSP 2206.

Product Name: SNAP 32R Retrofit fire collars protecting a nominal 32-mm PE-Xa Rehau Rautitan pipe penetrating a 40-mm diameter

aperture (Specimen 3)

Description:

The sponsor identified the specimen as retrofit fire collars protecting a steel framed plasterboard wall penetrated nine (9) pipes. The plasterboard wall was constructed in accordance with Boral Firestop system SB120.1 with an established fire resistance level (FRL) of -/120/120. Specimen 3 is the subject of this Certificate. The SNAP 32R Retrofit collar comprised a 0.75-mm steel casing with a 40 mm inner diameter and a 106-mm diameter base flange. The 32-mm high collar casing incorporated a closing mechanism which comprised two soft Intumesh intumescent strips lined within the internal circumference of the collar. The inner and outer strips were 4-mm thick x 26-mm wide x 135-mm long, and 4mm thick x 26-mm wide x 154-mm long, respectively. Between the strips was a layer of 316 stainless steel mesh 135 mm long x 25-mm wide with a wire mesh diameter of 0.15-mm. One collar was fixed to each side of the plasterboard wall in a back-to-back configuration using three 10 gauge 38-mm long coarse threaded laminating screws. The penetrating service comprised a Rehau Rautitan PE-Xa 32.2-mm outside diameter pipe, with a wall thickness of 4.6-mm fitted through the collar's sleeve and penetrated the wall through a 40 mm diameter cut-out hole. The pipe projected horizontally, 2000-mm away from the unexposed face of the wall and approximately 500 mm into the furnace chamber. The pipe was supported at nominally 500-mm and 1500-mm from the unexposed face of the plasterboard wall. The pipe was open at the unexposed end and plugged with ceramic fibre (Superwool) on the exposed end. The Sponsor provided document titled 'Plasterboard Fire and Acoustic Systems Australia', revision UB1231-SYS 12/18, by USG Boral Building Products Pty Ltd, drawing titled 'Specimen #3, 32 Pex-a Stack & 32R', dated 03 February 2021, by Snap Fire Systems Pty Ltd and drawing titled "SNAP 32 Retro", dated 5 October 2017, by Snap Fire Systems Pty Ltd as a complete description of the specimen and should be read in conjunction with this Certificate.

Performance observed in respect of the following AS 1530.4-2014 criteria

Structural Adequacy - not applicable
Integrity - no failure at 181 minutes
Insulation - no failure at 181 minutes

and therefore for the purpose of Building Regulations in Australia, achieved a fire-resistance level (FRL) of -/120/120.

The fire-resistance level is applicable when the system is exposed to fire from either direction. The test was conducted on a wall system with an established FRL of -/120/120. The maximum FRL of any test specimen cannot exceed the FRL achieved by the wall system in which it was installed. For the purposes of AS 1530.4-2014 the results of these fire tests may be used to directly assess fire hazard, but it should be noted that a single test method will not provide a full assessment of fire hazard under all fire conditions. This certificate is provided for general information only and does not comply with regulatory requirements for evidence of compliance.

Testing Officer: Peter Gordon

Issued on the 25th day of October 2021 without alterations or additions.

Brett Roddy | Manager, Fire Testing and Assessments

"Copyright CSIRO 2021 ©"
Copying or alteration of this report without written authorisation from CSIRO is forbidden

Date of Test:

8 June 2021



This document is issued in accordance with NATA's accreditation requirements.

Accreditation No. 165 – Corporate Site No. 3625

Accredited for compliance with ISO/IEC 17025 - Testing

www.cstro.au

14 Julius Avenue, North Ryde NSW 2113 PO Box 52, North Ryde NSW 1670, Australia T (02) 9490 5444 • ABN 41 687 119 230



Certificate of Test

No. 3616

This is to certify that the element of construction described below was tested by CSIRO Infrastructure Technologies in accordance with Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4 Fire-resistance tests of elements of construction, 2014, Section 10: Service penetrations and control joints, on behalf of:

IG6 Pty Ltd as trustee for the IG6 IP Trust

3 Skirmish Court

Victoria Point Qld 4165

A full description of the test specimen and the complete test results are detailed in the Division's report numbered FSP 2206.

Product Name: SNAP 32R Retrofit fire collars protecting a nominal 25-mm PE-Xa Rehau Rautitan pipe penetrating a 32-mm diameter

aperture (Specimen 4)

Description:

The sponsor identified the specimen as retrofit fire collars protecting a steel framed plasterboard wall penetrated nine (9) pipes. The plasterboard wall was constructed in accordance with Boral Firestop system SB120.1 with an established fire resistance level (FRL) of -/120/120. Specimen 4 is the subject of this Certificate. The SNAP 32R Retrofit collar comprised a 0.75-mm steel casing with a 40 mm inner diameter and a 106-mm diameter base flange. The 32-mm high collar casing incorporated a closing mechanism which comprised two soft Intumesh intumescent strips lined within the Internal circumference of the collar. The inner and outer strips were 4-mm thick x 26-mm wide x 135-mm long and 4-mm thick x 26-mm wide x 154-mm long respectively. Between the strips was a layer of 316 stainless steel mesh 135 mm long x 25-mm wide with wire mesh diameter of 0.15-mm. One collar was fixed to each side of the plasterboard wall in a back-to-back configuration using three 10 gauge 38-mm long coarse threaded laminating screws. The penetrating service comprised a Rehau Rautitan PE-Xa 25.1-mm outside diameter pipe, with a wall thickness of 3.73-mm fitted through the collar's sleeve and penetrated the wall through a 32 mm diameter cut-out hole. The pipe projected horizontally, 2000-mm away from the unexposed face of the wall and approximately 500 mm into the furnace chamber. The pipe was supported at nominally 500-mm and 1500-mm from the unexposed face of the plasterboard wall. The pipe was open at the unexposed end and plugged with ceramic fibre (Superwool) on the exposed end. The Sponsor provided document titled 'Plasterboard Fire and Acoustic Systems Australia', revision UB1231-SYS 12/18, by USG Boral Building Products Pty Ltd, drawing titled 'Specimen #4, 25 Pex-a Stack & 32R', dated 3 February 2021, by Snap Fire Systems Pty Ltd and drawing titled "SNAP 32 Retro", dated 5 October 2017, by Snap Fire Systems Pty Ltd as a complete description of the specimen and should be read in conjunction with this Certificate.

Performance observed in respect of the following AS 1530.4-2014 criteria

Structural Adequacy - not applicable Integrity - no failure at 181 minutes Insulation - 163 minutes

and therefore for the purpose of Building Regulations in Australia, achieved a fire-resistance level (FRL) of -/120/120.

The fire-resistance level is applicable when the system is exposed to fire from either direction. The test was conducted on a wall system with an established FRL of -/120/120. The maximum FRL of any test specimen cannot exceed the FRL achieved by the wall system in which it was installed. For the purposes of AS 1530.4-2014 the results of these fire tests may be used to directly assess fire hazard, but it should be noted that a single test method will not provide a full assessment of fire hazard under all fire conditions. This certificate is provided for general information only and does not comply with regulatory requirements for evidence of compliance.

Testing Officer: Peter Gordon

Issued on the 2Sth day of October 2021 without alterations or additions.

Date of Test: 8 June 2021

Brett Roddy | Manager, Fire Testing and Assessments

"Copyright CSIRO 2021 ©"
Copying or alteration of this report without written authorisation from CSIRO is forbidden



This document is issued in accordance with NATA's accreditation requirements.

Accreditation No. 165 – Corporate Site No. 3625

Accredited for compliance with ISO/IEC 17025 - Testing

www.cstro.au

14 Julius Avenue, North Ryde NSW 2113 PO Box 52, North Ryde NSW 1670, Australia T (02) 9490 5444 • ABN 41 687 119 230



Certificate of Test

No. 3617

This is to certify that the element of construction described below was tested by CSIRO Infrastructure Technologies in accordance with Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4 Fire-resistance tests of elements of construction, 2014, Section 10: Service penetrations and control joints, on behalf of:

IG6 Pty Ltd as trustee for the IG6 IP Trust

3 Skirmish Court Victoria Point Old 4165

A full description of the test specimen and the complete test results are detailed in the Division's report numbered FSP 2206.

Product Name: SNAP 32R Retrofit fire collars protecting a nominal 20-mm PE-Xa Rehau Rautitan pipe penetrating a 29-mm diameter

aperture (Specimen 5)

Description:

The sponsor identified the specimen as retrofit fire collars protecting a steel framed plasterboard wall penetrated nine (9) pipes. The plasterboard wall was constructed in accordance with Boral Fireston system SB120.1 with an established fire resistance level (FRL) of -/120/120. Specimen 5 is the subject of this Certificate. The SNAP 32R Retrofit collar comprised a 0.75-mm steel casing with a 40 mm inner diameter and a 106-mm diameter base flange. The 32-mm high collar casing incorporated a closing mechanism which comprised two soft Intumesh intumescent strips lined within the Internal circumference of the collar. The inner and outer strips were 4-mm thick x 26-mm wide x 135-mm long, and 4-mm thick x 26-mm wide x 154-mm long, respectively. Between the strips was a layer of 316 stainless steel mesh 135 mm long x 25-mm wide with wire mesh diameter of 0.15-mm. One collar was fixed to each side of the plasterboard wall in a back-to-back configuration using three 10 gauge 38-mm long coarse threaded laminating screws. The penetrating service comprised a Rehau Rautitan PE-Xa 20.2-mm outside diameter pipe, with a wall thickness of 3.5-mm fitted through the collar's sleeve and penetrated the wall through a 29 mm diameter cut-out hole. The pipe projected horizontally, 2000-mm away from the unexposed face of the wall and approximately 500 mm into the furnace chamber. The pipe was supported at nominally 500-mm and 1500-mm from the unexposed face of the plasterboard wall. The pipe was open at the unexposed end and plugged with ceramic fibre (Superwool) on the exposed end. The Sponsor provided document titled 'Plasterboard Fire and Acoustic Systems Australia', revision UB1231-SYS 12/18, by USG Boral Building Products Pty Ltd, drawing titled 'Specimen #5, 20 Pex-a Stack & 32R', dated 3 February 2021, by Snap Fire Systems Pty Ltd and drawing titled "SNAP 32 Retro", dated 5 October 2017, by Snap Fire Systems Pty Ltd as a complete description of the specimen and should be read in conjunction with this Certificate.

Performance observed in respect of the following AS 1530.4-2014 criteria

Structural Adequacy - not applicable Integrity - no failure at 181 minutes Insulation - 142 minutes

and therefore for the purpose of Building Regulations in Australia, achieved a fire-resistance level (FRL) of -/120/120.

The fire-resistance level is applicable when the system is exposed to fire from either direction. The test was conducted on a wall system with an established FRL of -/120/120. The maximum FRL of any test specimen cannot exceed the FRL achieved by the wall system in which it was installed. For the purposes of AS 1530.4-2014 the results of these fire tests may be used to directly assess fire hazard, but it should be noted that a single test method will not provide a full assessment of fire hazard under all fire conditions. This certificate is provided for general information only and does not comply with regulatory requirements for evidence of compliance.

Testing Officer: Peter Gordon

Issued on the 25th day of October 2021 without alterations or additions.

Brett Roddy | Manager, Fire Testing and Assessments

"Copyright CSIRO 2021 ©"
Copying or alteration of this report without written authorisation from CSIRO is forbidden

Date of Test:

8 June 2021



This document is issued in accordance with NATA's accreditation requirements.

Accreditation No. 165 – Corporate Site No. 3625

Accredited for compliance with ISO/IEC 17025 - Testing

www.cstro.au

14 Julius Avenue, North Ryde NSW 2113 PO Box 52, North Ryde NSW 1670, Australia T (02) 9490 5444 • ABN 41 687 119 230



Certificate of Test

No. 3618

This is to certify that the element of construction described below was tested by CSIRO Infrastructure Technologies in accordance with Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4 Fire-resistance tests of elements of construction, 2014, Section 10: Service penetrations and control joints, on behalf of:

IG6 Pty Ltd as trustee for the IG6 IP Trust

3 Skirmish Court

Victoria Point Qld 4165

A full description of the test specimen and the complete test results are detailed in the Division's report numbered FSP 2206.

Product Name: SNAP 32R Retrofit fire collars protecting a nominal 16-mm PE-Xa Rehau Rautitan pipe penetrating a 25-mm diameter

aperture (Specimen 6)

Description:

The sponsor identified the specimen as retrofit fire collars protecting a steel framed plasterboard wall penetrated nine (9) pipes. The plasterboard wall was constructed in accordance with Boral Firestop system SB120.1 with an established fire resistance level (FRL) of -/120/120. Specimen 6 is the subject of this Certificate. The SNAP 32R Retrofit collar comprised a 0.75-mm steel casing with a 40 mm inner diameter and a 106-mm diameter base flange. The 32-mm high collar casing incorporated a closing mechanism which comprised two soft Intumesh intumescent strips lined within the Internal circumference of the collar. The inner and outer strips were 4-mm thick x 26-mm wide x 135-mm long, and 4-mm thick x 26-mm wide x 154-mm long, respectively. Between the strips was a layer of 316 stainless steel mesh 135 mm long x 25-mm wide with wire mesh diameter of 0.15-mm. One collar was fixed to each side of the plasterboard wall in a back-to-back configuration using three 10 gauge 38-mm long coarse threaded laminating screws. The penetrating service comprised a Rehau Rautitan PE-Xa 16.1-mm outside diameter pipe, with a wall thickness of 2.6-mm fitted through the collar's sleeve and penetrated the wall through a 25 mm diameter cut-out hole. The pipe projected horizontally, 2000-mm away from the unexposed face of the wall and approximately 500 mm into the furnace chamber. The pipe was supported at nominally 500-mm and 1500-mm from the unexposed face of the plasterboard wall. The pipe was open at the unexposed end and plugged with ceramic fibre (Superwool) on the exposed end. The Sponsor provided document titled 'Plasterboard Fire and Acoustic Systems Australia', revision UB1231-SYS 12/18, by USG Boral Building Products Pty Ltd, drawing titled 'Specimen #6, 16 Pex-a Stack & 32R', dated 3 February 2021, by Snap Fire Systems Pty Ltd and drawing titled "SNAP 32 Retro", dated 5 October 2017, by Snap Fire Systems Pty Ltd as a complete description of the specimen and should be read in conjunction with this Certificate.

Performance observed in respect of the following AS 1530.4-2014 criteria

Structural Adequacy - not applicable Integrity - no failure at 181 minutes Insulation - 175 minutes

and therefore for the purpose of Building Regulations in Australia, achieved a fire-resistance level (FRL) of -/120/120.

The fire-resistance level is applicable when the system is exposed to fire from either direction. The test was conducted on a wall system with an established FRL of -/120/120. The maximum FRL of any test specimen cannot exceed the FRL achieved by the wall system in which it was installed. For the purposes of AS 1530.4-2014 the results of these fire tests may be used to directly assess fire hazard, but it should be noted that a single test method will not provide a full assessment of fire hazard under all fire conditions. This certificate is provided for general information only and does not comply with regulatory requirements for evidence of compliance.

Testing Officer: Peter Gordon

Issued on the 2Sth day of October 2021 without alterations or additions.

Brett Roddy | Manager, Fire Testing and Assessments

"Copyright CSIRO 2021 ©"
Copying or alteration of this report without written authorisation from CSIRO is forbidden

Date of Test:

8 June 2021



This document is issued in accordance with NATA's accreditation requirements.

Accreditation No. 165 – Corporate Site No. 3625

Accredited for compliance with ISO/IEC 17025 - Testing

www.cstro.au

14 Julius Avenue, North Ryde NSW 2113 PO Box 52, North Ryde NSW 1670, Australia T (02) 9490 5444 • ABN 41 687 119 230



Certificate of Test

No. 3619

This is to certify that the element of construction described below was tested by CSIRO Infrastructure Technologies in accordance with Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4 Fire-resistance tests of elements of construction, 2014, Section 10: Service penetrations and control joints, on behalf of:

IG6 Pty Ltd as trustee for the IG6 IP Trust

3 Skirmish Court Victoria Point Old 4165

A full description of the test specimen and the complete test results are detailed in the Division's report numbered FSP 2206.

Product Name: SNAP 32R Retrolit fire collars protecting a nominal 25-mm Pex-Al-Pex pipe penetrating a 32-mm diameter aperture

(Specimen 8)

Description:

The sponsor identified the specimen as retrofit fire collars protecting a steel framed plasterboard wall penetrated nine (9) pipes. The plasterboard wall was constructed in accordance with Boral Fireston system SB120.1 with an established fire resistance level (FRL) of -/120/120. Specimen 8 is the subject of this Certificate. The SNAP 32R Retrofit collar comprised a 0.75-mm steel casing with a 40-mm inner diameter and a 106 mm diameter base flange. The 32-mm high collar casing incorporated a closing mechanism which comprised two soft Intumesh intumescent strips lined within the Internal circumference of the collar. The inner and outer strips were 4-mm thick x 26-mm wide x 135-mm long, and 4-mm thick x 26-mm wide x 154-mm long, respectively. Between the strips was a layer of 316 stainless steel mesh 135 mm long x 25-mm wide with wire mesh diameter of 0.15-mm. One collar was fixed to each side of the plasterboard wall in a back-to-back configuration using three 10 gauge 38-mm long coarse thread laminating screws. The penetrating service comprised a CXL Pex-Al-Pex 25.15-mm outside diameter pipe, with a wall thickness of 2.75-mm fitted through the collar's sleeve and penetrated the wall through a 32-mm diameter cut-out hole. The pipe projected horizontally, 2000-mm away from the unexposed face of the wall and approximately 500 mm into the furnace chamber. The pipe was supported at nominally 500-mm and 1500-mm from the unexposed face of the plasterboard wall. The pipe was open at the unexposed end and plugged with ceramic fibre (Superwool) on the exposed end. The Sponsor provided document titled 'Plasterboard Fire and Acoustic Systems Australia', revision UB1231-SYS 12/18, by USG Boral Building Products Pty Ltd, drawing titled 'Specimen #8 25 Pex-Al-Pex Stack & 32R', dated 3 February 2021, by Snap Fire Systems Pty Ltd and drawing titled "SNAP 32 Retro", dated 5 October 2017, by Snap Fire Systems Pty Ltd as a complete description of the specimen and should be read in conjunction with this Certificate.

Performance observed in respect of the following AS 1530.4-2014 criteria

Structural Adequacy - not applicable Integrity - no failure at 181 minutes Insulation - 159 minutes

and therefore for the purpose of Building Regulations in Australia, achieved a fire-resistance level (FRL) of -/120/120.

The fire-resistance level is applicable when the system is exposed to fire from either direction. The test was conducted on a wall system with an established FRL of -/120/120. The maximum FRL of any test specimen cannot exceed the FRL achieved by the wall system in which it was installed. For the purposes of AS 1530.4-2014 the results of these fire tests may be used to directly assess fire hazard, but it should be noted that a single test method will not provide a full assessment of fire hazard under all fire conditions. This certificate is provided for general information only and does not comply with regulatory requirements for evidence of compliance.

Testing Officer: Peter Gordon

Issued on the 25th day of October 2021 without alterations or additions.

Brett Roddy | Manager, Fire Testing and Assessments

"Copyright CSIRO 2021 ©"
Copying or alteration of this report without written authorisation from CSIRO is forbidden

Date of Test:

8 June 2021



This document is issued in accordance with NATA's accreditation requirements.

Accreditation No. 165 – Corporate Site No. 3625

Accredited for compliance with ISO/IEC 17025 - Testing

www.cstro.au

14 Julius Avenue, North Ryde NSW 2113 PO Box 52, North Ryde NSW 1670, Australia T (02) 9490 5444 • ABN 41 687 119 230



Certificate of Test

No. 3620

This is to certify that the element of construction described below was tested by CSIRO Infrastructure Technologies in accordance with Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4 Fire-resistance tests of elements of construction, 2014, Section 10: Service penetrations and control joints, on behalf of:

IG6 Pty Ltd as trustee for the IG6 IP Trust

3 Skirmish Court Victoria Point Old 4165

A full description of the test specimen and the complete test results are detailed in the Division's report numbered FSP 2206.

Product Name: SNAP MS70R Multi Services Retrofit fire collars protecting a nominal 32 (42.2-mm OD) PN12 PVC pipe with 19-mm thick

fire rated lagging penetrating a 70-mm diameter aperture (Specimen 9)

Description:

The sponsor identified the specimen as retrofit fire collars protecting a steel framed plasterboard wall penetrated nine (9) pipes. The plasterboard wall was constructed in accordance with Boral Fireston system SB120.1 with an established fire resistance level (FRL) of -/120/120. Specimen 9 is the subject of this Certificate. The SNAP MS70R Multi Service Retrofit fire collar comprised a 0.75-mm thick steel casing with a 69-mm inner diameter and a 0.95-mm thick steel base flange with a 162-mm diameter. The 95 mm high collar casing incorporated a 4-mm thick x 90-mm wide x 250-mm long soft Intumesh intumescent wrap lined within the internal circumference of the collar casing. The closing mechanism comprised three stainless steel springs, a nylon fuse link and a 258-mm long x 88-mm wide 316 stainless steel mesh located around the intumescent strip. One collar was fixed to each side of the plasterboard wall in a back-to-back configuration using three M4 expandable steel hollow wall anchors with stainless steel washers. The penetrating service comprised a Iplex PN12 PVC 42.2-mm outside diameter pipe, with a wall thickness of 2.57-mm covered with 19-mm thick Armaflex FR foam lagging. The lagged pipe was fitted through the collar's sleeve and penetrated the wall through a 70-mm diameter cut-out hole. The lagged pipe projected horizontally 2000-mm away from the unexposed face of the wall and approximately 500 mm into the furnace chamber. The lagged pipe was supported at 500 mm and 1500-mm from the unexposed face of the plasterboard wall. The pipe was open at the unexposed end and plugged with ceramic fibre (Superwool) on the exposed end. The Sponsor provided document titled 'Plasterboard Fire and Acoustic Systems Australia', revision UB1231-SYS 12/18, by USG Boral Building Products Pty Ltd, drawing titled 'Specimen #9 32 PN12 PVC Pipe with 19mm F/R Lagging & MS70R Collar', dated 3 February 2021, by Snap Fire Systems Pty Ltd and drawing titled 'SNAP 70 Multi Service Retro', dated 23 September 2019, by Snap Fire Systems Pty Ltd as a complete description of the specimen and should be read in conjunction with this Certificate.

Performance observed in respect of the following AS 1530.4-2014 criteria

Structural Adequacy - not applicable
Integrity - no failure at 181 minutes
Insulation - 181 minutes

and therefore for the purpose of Building Regulations in Australia, achieved a fire-resistance level (FRL) of -/120/120.

The fire-resistance level is applicable when the system is exposed to fire from either direction. The test was conducted on a wall system with an established FRL of -/120/120. The maximum FRL of any test specimen cannot exceed the FRL achieved by the wall system in which it was installed. For the purposes of AS 1530.4-2014 the results of these fire tests may be used to directly assess fire hazard, but it should be noted that a single test method will not provide a full assessment of fire hazard under all fire conditions. This certificate is provided for general information only and does not comply with regulatory requirements for evidence of compliance.

Testing Officer: Peter Gordon Date of Test: 8 June 2021

Issued on the 25th day of October 2021 without alterations or additions.

Brett Roddy | Manager, Fire Testing and Assessments

"Copyright CSIRO Z021 ©"
Copying or alteration of this report without written authorisation from CSIRO is forbidden



This document is issued in accordance with NATA's accreditation requirements.

Accreditation No. 165 – Corporate Site No. 3625

Accredited for compliance with ISO/IEC 17025 - Testing

References

The following informative documents are referred to in this Report:

AS 1530.4-2014	Methods for fire tests on building materials, components and structures Part 4: Fire-resistance tests for elements of building construction.
AS 4072.1-2005	Components for the protection of openings in fire-resistant separating elements. Part 1: Service penetrations and control joints.

CONTACT US

- t 1300 363 400 +61 3 9545 2176
- e enquiries@csiro.au
- w www.csiro.au

YOUR CSIRO

Australia is founding its future on science and innovation. Its national science agency, CSIRO, is a powerhouse of ideas, technologies and skills for building prosperity, growth, health and sustainability. It serves governments, industries, business and communities across the nation.

FOR FURTHER INFORMATION

Infrastructure Technologies

Brett Roddy

Team Leader, Fire Testing and Assessments

- t +61 2 94905449
- e brett.roddy@csiro.au
- **w** https://www.csiro.au/en/Do-business/Services/Materials-infrastructure/Fire-safety